**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**LG Electronics India Pvt Ltd**
Plot No . A-5| MIDC, Ranjangaon,
Tal: Shirur ,Dist: Pune - 412 220
Maharashtra -India

**Date : 10.10.2019**
Quote NO : SQT.19.20.2123R1
**Kind Attn : Mr. MANTHESH PATIL**
Email Id : mahantesh.patil@lge.com
Contact No: **9168600204**

**Project Name & Location: LG Electronics India Pvt Ltd , Pune**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 2 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | PIT MOUNTED ELECTRO HYDRAULIC SCISSOR LIFT | 1200 | 2000 | 1 | 264,000 | 264,000 | 20,000 | 20,000 |
| | | | | **Total** | | **264,000** | | **20,000** |
| 2 | | | P&F Charges | 3% | | **7,920** | | |
| | | | **Total Without Taxes** | | | **271,920** | | **20,000** |
| | | | GST Extra @ 18% | 18% | | 48,946 | | 3,600 |
| | | | **Total With Taxes** | | | **320,866** | | **23,600** |
| 3 | | | Transportation Charges | | | **In Client Scope** | | |
| 4 | | | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**PIT MOUNTED ELECTRO HYDRAULIC SCISSOR LIFT**

| Description | Specification |
|---|---|
| Capacity | 250 kgs |
| Platform Size | 2000L x 1200W |
| Shut ht | 300 mm |
| Max ht | 1300 mm |
| Lift ht | 1000 mm |
| Power pack | 2HP, 3Phase |
| Safty | Safty Bellow from all Side. |
| REQ. PIT SIZE | 2050L X 1350W X 310H |
| Railing | Only two side 300 mm height on platform. |
| Colour | As required |

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd