NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/19-20/1788 **Date : 08.07.2019**

LM Wind Power Blades
Bangalore

Kind Attn : Mr. Santosh Naik
Email ID : Santosh.NaikG@lmwindpower.com
Contact No : +91 9880942200

Project Name And Location : Pin Join Facility_Bangalore

Subject : Quotation for Rolling Shutter, High Speed Door, Dock Leveller, Double Wall Rolling Shutter, Sliding Gate

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Motor - Indirect Drive Motor** **• With Painting** **• Extra Push Button** **• Yellow Flashing Light** **• MS Strcture for Rolling Shutter** **(Supply + Installation + Unloading + Transport)**				
1	Size (W) 3200 mm x (H) 3500 mm	1	No	161,000	161,000
2	Size (W) 3200 mm x (H) 3000 mm	2	No	150,000	300,000
B	**Automation for Existing Shutters** **Technical Specifications:** **• Motor - Indirect Drive Motor** **• With Painting** **• Extra Push Button** **• Yellow Flashing Light** **(Supply + Installation + Unloading + Transport)**				
1	Size (W) 3500 mm x (H) 4400 mm	3	No	88,000	264,000
C	**NIHVA ASSA ABLOY High Speed Doors HS9020G (100% Imported from Germany)** **Technical Specifications:** **• Operating speed : Opening: up to 1,2 m/s 2, closing: 0,5 m/s .** **The fast opening and closing speed improves your traffic flow, provides employee comfort, and saves energy.** **• Wind load resistance : Class 1 (300 N/m2), maximum wind load while closing 50 N/m2** **• Bottom Edge : The soft bottom edge has no rigid parts, it moulds around any obstruction to prevent injury or damage** **• Self Repairable Function : When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side** **guides without causing damage or being damaged itself.** **• Vision Window - One row of 400 mm height** **• Yellow Flashing Light** **• Safety : Safety Bottom Edge, Photocell, Remote and Receiver** **(Supply + Installation + Unloading + Transport)**				
1	Size (W) 3200 mm x (H) 3000 mm	2	No	580,500	1,161,000
2	Size (W) 3500 mm x (H) 4000 mm	1	No	634,500	634,500

D	**Motorized Double Wall Rolling Shutter** **Technical Specifications:** **• GI Slat : 19 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Motor - Direct Drive Motor** **• With Painting** **• Extra Push Button** **• Yellow Flashing Light** **• Remote Control** **• MS Strcture for Rolling Shutter** **(Supply + Installation + Unloading + Transport)** 				
1	Size (W) 3500 mm x (H) 4000 mm	2	No	422,000	844,000
E	**Dock Leveler (NIHVA Make)** 2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers. **Specifications :** **• Capacity - 9 Ton** **• Loading platform height from road - 1250 mm** **• Deck Plate Thickness - 8 mm** **• Lip Plate Thickness - 16 mm** **• Travel above & below dock level - (+) 300 / (-) 250 mm** **• Platform Size (W x L) - 2300 mm x 2900 mm** **• Lip size (W x L) - 2000 mm x 400 mm** **• Shut Height - 480 mm** **• Clear Pit dimensions (W x L x D) - (W) 2350mm x (L) 2900 mm x (D) 485 mm** 				
1	**Dock Levelers Capacity 9 Ton** Size : (W) 2300 mm X (L) 2900 mm X (H) 480mm (Supply + Installation + Unloading + Transport)	3	No	220,000	660,000

F	**Automatic Two Leaf Telescopic Sliding Gate** **• Outer Tube - 72 x 72 x 3.2 mm** **• Inner Tube - 38 x 38 x 2.6 mm** **• Gap Between Tubes - 125 mm** **• Post Size - 72 x 72 x 3.2 mm** **• Motor - European make** **• Telescopic Mechanism** **• Photocell** **• Flashing Light** **• Rack & Pinion** **• Electrical wire & accesories** **(Supply + Installation + Unloading + Transport)** 				
1	Size (W) 15500 mm x (H) 1200 mm	1	No	1,015,000	1,015,000
G	**Automatic Single Leaf Cantilever Sliding Gate** **• Outer Tube - 72 x 72 x 3.2 mm** **• Inner Tube - 38 x 38 x 2.6 mm** **• Gap Between Tubes - 125 mm** **• Post Size - 72 x 72 x 3.2 mm** **• Motor - European make** **• Cantilever Machanism** **• Photocell** **• Flashing Light** **• Rack & Pinion** **• Electrical wire & accesories** **(Supply + Installation + Unloading + Transport)** 				
1	Size (W) 6500 mm x (H) 1200 mm	1	No	615,000	615,000
2	Size (W) 5000 mm x (H) 1200 mm	1	No	575,000	575,000

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**6,229,500**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope. - **NIHVA Scope**

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site - **NIHVA Scope**
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	At Site
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Included
4	**Delivery**	:	5 - 6 weeks for Rolling Shutter, Dock Leveller and Gates and 12 -13 weeks for High Speed Doors- from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Tax**	:	GST@18% Extra
7	**Validity**	:	Validity of Offer is 15 days from the date of quotation
8	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact Arjun Patil on **8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd