NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1832 **Date :20.07.2019**

Shapoorji Pallonji & Company Pvt Ltd
SP Infocity, Incubator No. 4,
Pune - Saswad Road, Phursungi,
Pune - 412308

Kind Attention : **Jilan Gandhi**
Email ID : jilan.gandhi@shapoorji.com
Contact No : 7624009545

Project Name And Location : Development of Mumbai- Ahmedabad High Speed Rail.

Subject : Quotation for 2 Hrs Fire Rated Rolling Shutter and Sliding Hangar door .

Dear Sir

Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**2 Hrs. Fire Rated Motorized Rolling Shutters (BS476) -100% IMPORTED** **• Shutter Slats: Zinc coated steel solid slats** **• Slat Thickness: 1.0mm thick** **• Shutter Guide: Fabricated from hot-dipped galvanised steel of 3.0mm.** **• Operated by: Motor with one unit push button switch & manual override**				
1	Size : (W) 10000 mm x(H)7850 mm **(Supply + Installation)**	6	No	978,000	5,868,000
2	Size : (W) 3850 mm x (H)2500 mm **(Supply + Installation)**	6	No	227,000	1,362,000
3	Size : (W) 4000 mm x (H) 3500 mm **(Supply + Installation)**	6	No	268,000	1,608,000
4	Size : (W) 4260 mm x (H)2500mm **(Supply + Installation)**	3	No	236,000	708,000
5	Size : (W) 5700 mm x (H)2500 mm **(Supply + Installation)**	12	No	282,000	3,384,000
6	Size : (W) 85000 mm x (H)6500 mm **(Supply + Installation)**	24	No	733,000	17,592,000
7	Size : (W) 2500 mm x (H)2500 mm **(Supply + Installation)**	3	No	197,000	591,000
8	Size : (W) 4260mm x (H)2500 mm **(Supply + Installation)**	2	No	236,000	472,000
9	Size : (W) 7500 mm x (H)2500 mm **(Supply + Installation)**	2	No	340,000	680,000
10	Size : (W) 3000 mm x (H)4700 mm **(Supply + Installation)**	6	No	274,000	1,644,000
11	Size : (W) 4500 mm x (H) 4700 mm **(Supply + Installation)**	3	No	350,000	1,050,000
12	Size : (W) 3200 mm x (H)3000 mm **(Supply + Installation)**	3	No	342,000	1,026,000
13	Size : (W) 8500 mm x (H)5500 mm **(Supply + Installation)**	3	No	669,000	2,007,000
14	Size : (W) 8400 mm x (H)3000 mm **(Supply + Installation)**	6	No	396,000	2,376,000
15	Size : (W)11100 mm x (H)1000 mm **(Supply + Installation)**	15	No	577,000	8,655,000
16	Size : (W) 10225 mm x (H)5300 mm **(Supply + Installation)**	2	No	731,000	1,462,000
17	Size : (W) 8750 mm x (H)5300 mm **(Supply + Installation)**	2	No	667,000	1,334,000
				Total	**51,819,000**
B	**Sliding Hangar Door**				
1	Size : (W)5500 mm x(H)6500 mm **(Supply + Installation)**	8	No	1,250,000	10,000,000
				Total	**10,000,000**

GST Pune	**27AAECN0437H1ZM**	**Total**	**61,819,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra As applicable.
4	**Delivery**	:	8 -9 weeks for Fire Rated Rolling Shutter, 10 - 12 Weeks For hangar Door.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18% Extra
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Bhavin Jain** on **8551092333** For any further Clarification in this concern

With Best Regards

Ulka Auti

7219206333

For Nihva Technologies Pvt Ltd