NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tech Expert Engineering Pvt Ltd
116, Siddharth Towers,
First Floor, Karve Road,
Kothrud, Pune - 411038 India.

Date : 11.06.2020
Quote NO : SQT.19.20.2604
Kind Attn : Mr. Prashant Hebare
Email Id : prashant.hebare@techexpertindia.com
Contact No: 9370150718

Project Name & Location: Pune.

Subject : Quotation for Fire Rated Motorised Rolling Shutter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Fire Rated Motorised Rolling Shutter**	4200	5800	1	422,000	422,000	20,000	20,000
				Total Value		**422,000**		**20,000**
				P&F Charges	3%	12,660		
				Total Without Taxes		**434,660**		**20,000**
				GST Extra @ 18%	18%	78,239		3,600
				Total With Taxes		**512,899**		**23,600**
				Total (Supply + Installtion) with Taxes				**536,499**
2				Transportation Charges		**In Client Scope**		
3				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

Design:
Roll formed from 1st grade BHP Zincalume steel curve slat curtain

Guide Rail:
Fabricated from hot-dipped galvanized steel of 3.0mm with one-piece design surface mounted type

Bottom Bar:
Assembled of 2 pieces of 38x38x3mm galvanized steel angle bolted 800mm pitch with galvanized bolts and nuts or 2 pieces of 40x40x6mm steel flat bar.

Shutter Enclosure Box:
Fabricated from heavy duty 7.0mm steel plate for both ends and supports with steel frame with very well black primer one coat. Box covers shall be of 0.8mm steel sheets with BHP zincalume finishing.

Motor Drive Unit:
- **Power Source:**
  230v 50Hz 1 phase
- **Manual Chain Override**
- **One-unit push button switch**
- **Gravity drop level**
- **Fire Shutter will autoclose via 71 Degree Celcius Thermal Fusible Link**
- **Auto close by relay switch after receive of 24vdc fire signal**

Standard RAL colors:
- **RAL 1015**
- **RAL 7025**
- **RAL 9010**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 8 - 9 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 18 months from the date of Installation.(Subject to date of installation within one month from date of supply)

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333.**

With Best Regards
Ulka
7219206333
For NIHVA Technologies Pvt Ltd