**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**DSV Air & Sea Pvt. Ltd**
The Qube , B-201, B-204 , M.V. Road
Off International Airport Approach Road
Marol, Andheri East , Mumbai – 400059 , INDIA

**Date : 12.11.2020**
Quote NO : SQT.20.21.2825
**Kind Attn :** Mr. Nilesh Kawale
Email Id : naresh.kawale@in.dsv.com
Contact No: 9819015944

**Project Name & Location:** Gurgaon

**Subject : Quotation for Dock Leveler**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **NIHVA Dock Leveler**<br>**Capacity 6 Ton Point Load ( 15 Ton UDL)** | 2000 | 2500 | 5 | 225,000 | 1,125,000 | 20,000 | 100,000 |
| | | | | **Total** | | **1,125,000** | | **100,000** |
| 4 | P&F Charges | | | 3% | | **33,750** | | |
| | **Total Without Taxes** | | | | | **1,158,750** | | **100,000** |
| | GST Extra @ 18% | | | 18% | | 208,575 | | 18,000 |
| | **Total With Taxes** | | | | | | | **118,000** |
| 5 | Transportation Charges | | | | | **In client scope** | | |
| 6 | Unloading Charges @ Site | | | | | **In client scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**NIHVA Dock Leveler**

| Sr. No | Description | Specifications For 6 Ton |
|---|---|---|
| 1 | Required Capacity | 6 Ton Point Load ( 15 Ton UDL) |
| 2 | Hydraulic Power pack | 1 HP, 3PH |
| 3 | Control Panel | 4 Push Button operated |
| 4 | Deck operation | By push button Deck UP & Deck Down |
| 5 | Lip operation | By push button Deck UP & Deck Down |
| 6 | Loading platform height from road Level | 4 feet (1200 mm) |
| 7 | Travel above from Dock level height | 350 mm |
| 8 | Travel below from Dock level height | 200 mm |
| 9 | Platform size | 2000mm (W) x 2500 mm (L) |
| 10 | Lip sizes | 400 mm |
| 11 | Clear Pit dimensions | 2040mm (W) x 2500mm (L) x 485mm (H) |
| 12 | Drive type | Direct by electric Motor |
| 13 | Power Consumption | 0.75 kw Motor |
| 14 | Degree of protection for motor | IP 55 |
| 15 | Motor RPM | 1410 rpm |
| 16 | Pump design flow | 1.8 LPM |
| 17 | Pump pressure | 200 bar |
| 18 | Safety valve set pressure | 90 bar |
| 19 | Pump type | Gear |
| 20 | In built safety valve | Yes |
| 21 | Volume of oil receiver | 8 Ltr |
| 22 | No of Deck Cylinders | 2 Nos |
| 23 | Deck Plate Thickness | 8 mm Chequered Plate |
| 24 | No of Lip Cylinders | 1 No |
| 25 | Lip Plate | 16 mm Thick Plate |
| 26 | Dock Bumpers | 1 Pair included |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | |
| 4 | Any civil / masonry/structural work required | |
| 5 | All structure support required | |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | |
| 7 | Conduits, Cables required | |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks for Dock Leveler from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd