SAME DEUTZ-FAHR INDIA (P) LIMITED

TECHNICAL SPECIFICATION FOR SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF DOCK LEVELER

General:

This dock leveler shall be installed in the proposed expansion project at **Same Deutz-Fahr India Pvt Ltd, Ranipet**

Scope of supply:

Provide telescopic type dock levelers of type, function, operation, capacity, size, and construction indicated, complete with controls, safety devices, and accessories required. The Scope of supply shall include but not be limited to the following along with necessary fittings, fixtures and ancillaries. The design & supply of equipment needs to confirm to requirements of DISH,Statutory requirements.

Type:

Provide self-supporting frame, with an Electro-hydraulic mechanism, hinged-lip-type dock levelers designed for permanent installation in concrete pits, preformed in the edge of loading platform. Operation pilot - controlled with the door.

Function:

Dock levelers shall compensate for differences in height between truck bed and loading platform in the following manner:

• Vertical Travel: Please refer the excel work sheet dock leveler requirement for the vertical requirement of all the dock levelers. Provide an operating range above platform level of sufficient height to enable lip to extend and clear truck bed before contact.
• Automatic Vertical Compensation: Floating travel of ramp with lip extended and resting on truck bed shall compensate automatically for upward or downward movement of truck bed during loading and unloading.
• Automatic Lateral Compensation: Tilting of ramp with lip extended and resting on truck bed shall compensate automatically for canted truck beds of up to 100mm over width of ramp.
• Lip Operation: Provide manufacturer's standard mechanism that automatically extends and supports the telescopic lip on ramp edge with lip resting on truck bed over dock leveler's

working range, allows lip to yield under impact of incoming truck, and automatically retracts lip when truck departs.

• Length of Lip Extension: Refer the excel file dock leveler requirement for length of lip extension for all the 7 dock levelers

Operation:

Provide manufacturer's standard operating system as follows:

• Mechanical Operating System: Provide spring-operated raising and walk-down lowering of unloaded ramp. Equip units with an upward-biased-spring counterbalancing mechanism controlled by a hold-down device. Raise ramp to top limit of operating range by operating recessed control handle in ramp to disengage hold-down device. Lower ramp below platform level with lip retracted by operating auxiliary, recessed, control handle to release support legs.

Rated Capacity:

Provide dock levelers capable of supporting a total gross load indicated below without permanent deflection or distortion, as determined by actual tests complying with requirements of MH 30.1 for rated capacity.

• Total Load: 20 T capacity UDL and 15 T point load

• Minimum Length (without Lip): 2500 mm

• Minimum width: 2000 mm to 2200 mm as given in the excel file dock leveler requirement

Safety Devices:

Provide manufacturer's standard and optional safety devices as follows:

• Toe Guards: Equip open sides of rising ramp over entire upper operating range with metal toe guards mounted flush with ramp edges and projecting below ramp.

• Cross-Traffic Support: Provide manufacturer's standard method of supporting ramp at platform level in stored position with lip retracted. Provide a means to release supports to allow ramp to descend below platform level.

• Free-Fall Protection: Equip mechanical dock levelers with manufacturer's standard protection system to limit free fall of loaded ramps with front edge supported by truck bed.

• Maintenance Strut: Provide an integral strut to positively support ramp in up position during maintenance of dock leveler.

***The equipment needs to be designed for best, safe for operation & maintenance application.**

*** The equipment as whole or partly shall not become obsolete for the next 10 years' time & supplier needs to provide spares, service support within 24 hours of intimation.**

• Interlocks: Provide control interlocks between dock leveler and other dock equipment as follows:

• Leveler to Truck-Restraint Interlock: Leveler will not operate while truck restraint is not engaged.

Construction:

Fabricate dock-leveler frame from structural- and formed-steel shapes. Fabricate platform, including hinged lip, from nonskid steel plate. Fabricate entire assembly to withstand deformation during both operating and stored phases of service. Chamfer lip edge to minimize obstructing wheels of material-handling vehicles. Include two dock bumpers attached to frame.

Clean Pit Frame:

Provide leveler framing designed to support leveler at sides of pit, with no side-to-side supports at front and back of pit floor.

Finish and Color:

Manufacturer's standard paint, powder coated applied to factory-assembled and - tested dock levelers before shipping. Paint toe guards yellow to comply with ANSI Z535.1. The finishes shall be as per client's requirement at site.

Accessories:

Equip units with manufacturer's standard accessories as follows:

• Night Locks: Provide manufacturer's standard means to prevent extending lip and lowering ramp when overhead doors are locked.

• Side and rear weather seals.

• Foam insulation under dock-leveler platform.

Documentation

Supplier need to provide GA drawings & 3 sets of complete set of manuals for operation, maintenance, spare parts, circuit drawings etc. in hard & soft copies.