NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shapoorji Pallonji And Company Private Limited,
Chennai

Date : 22.01.2021
Quote NO : SQT.20-21.2934 R
Kind Attn : DHIAGARAJAN.G
Email Id : DHIAGARAJAN.GUNASEKARAN@shapoorji.com
Contact No: 9750170016

Subject : Quotation for High Speed Door, Dock Leveller, Rolling Shutter and Motorised Single Leaf Sliding Gate - M/S OLA Elec. Project

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	All type of doors specified as per BOQ (Supply + Installation)						**Inclusive**	
16 - a)	**Motorised Single Leaf Sliding Gate**	12000	1800	3	400,541	1,201,623	**Inclusive**	
	Motorised Single Leaf Sliding Gate	10000	1800	1	373,054	373,054	**Inclusive**	
	Motorised Single Leaf Sliding Gate	9000	1800	1	350,501	350,501	**Inclusive**	
	Wicket Gate	1000	1800	5	45,000	225,000	**Inclusive**	
	NIHVA Make Dock Leveller	2250	2500	100	210,000	21,000,000	**Inclusive**	
	NIHVA Make High Speed Door	3000	3000	4	198,000	792,000	**Inclusive**	
	NIHVA Make High Speed Door	4000	4000	16	219,000	3,504,000	**Inclusive**	
	NIHVA Make High Speed Door	4000	5000	150	235,000	35,250,000	**Inclusive**	
	G I Motorised Rolling Shutter - Direct Drive	3000	3000	2	120,000	240,000	**Inclusive**	
	SINGLE LEAF FIRE RATED DOOR - 2 HOURS FIRE RATING - Specifications as per BOQ					-	**Inclusive**	
	DOOR SIZE : 1200 x 2400mm (With Panic bar)	1200	2400	76	52,169	3,964,844	**Inclusive**	
	SINGLE LEAF FIRE RATED DOOR - 2 HOURS FIRE RATING - Specifications as per BOQ					-	**Inclusive**	
	DOOR SIZE : 1200 x 2400mm (with out panic bar)	1200	2400	51	44,924	2,291,124	**Inclusive**	
	DOUBLE LEAF EQUAL SHUTTER FIRE RATED DOOR - 2 HOURS FIRE RATING - Specifications as per BOQ						**Inclusive**	
	DOOR SIZE : 1800 x 2400mm (with out panic bar)	1800	2400	43	84,046	3,613,978	**Inclusive**	
	Application : Shaft doors						**Inclusive**	
	TRAP DOOR - Single shutter - (2H/FIRE RATED STEEL DOOR WITHOUT VISION PANEL) - 750 mm x 1500 mm with hardwares	750	1500	9	10,768	96,912	**Inclusive**	
	TRAP DOOR - Single shutter - (2H/FIRE RATED STEEL DOOR WITHOUT VISION PANEL) - 900 mm x 1500 mm with hardwares	900	1500	9	12,149	109,341	**Inclusive**	
	TRAP DOOR - Double shutter - (2H/FIRE RATED STEEL DOOR WITHOUT VISION PANEL) -1000 mm x 1500 mm with hardwares	1000	1500	9	16,346	147,114	**Inclusive**	

	120Mins. Fire rated hollow metal door with vision panel - Painted						**Inclusive**	
	FRD1 - 1200 mm x 2400 mm - Single leaf door with vision panel Panic bar and hardware set as per drawing	1200	2400	9	52,169	469,521	**Inclusive**	
	FRD2 - 1200 mm x 2400 mm - Single leaf door with vision panel and hardware set as per drawing	1200	2400	12	44,924	539,088	**Inclusive**	
	FRD3 - 1500 mm x 2400 mm - Double leaf door with vision panel and hardware set as per drawing	1500	2400	11	79,626	875,886	**Inclusive**	
	FRD4 - 1500 mm x 2400 mm - Double leaf unequal door with vision panel and hardware set as per drawing	1500	2400	4	65,158	260,632	**Inclusive**	
	FRD5 - 2000 mm x 2400 mm - Double leaf door with vision panel, Panic bar and hardware set as per drawing	2000	2400	4	103,080	412,320	**Inclusive**	
	FRD5 - 2000 mm x 2400 mm - Double leaf door with vision panel and hardware set as per drawing	2000	2400	2	86,992	173,984	**Inclusive**	
	General Steel doors - Painted					-		
	SD1 -Steel Door - Without Firerated (Single Shutter) - 1000 mm x 2400 mm	1000	2400	2	28,475	56,950	**Inclusive**	
	SD2 -Steel Door - Without Firerated (Single Shutter) - 1200 mm x 2400 mm	1200	2400	1	33,664	33,664	**Inclusive**	
	Application : Shaft doors					-	**Inclusive**	
	TD1 - TRAP DOOR (2H/FIRE RATED STEEL DOOR WITHOUT VISION PANEL) - 1000 mm x 1500 mm with hardwares	1000	1500	12	13,071	156,852	**Inclusive**	
	TD2 - TRAP DOOR (2H/FIRE RATED STEEL DOOR WITHOUT VISION PANEL) - 750 mm x 1500 mm with hardwares	750	1500	22	10,768	236,896	**Inclusive**	
	TD3 - TRAP DOOR (2H/FIRE RATED STEEL DOOR WITHOUT VISION PANEL) - Double Shutter 1000 mm x 1500 mm with hardwares	1000	1500	8	16,346	130,768	**Inclusive**	
	System for Standard (Straight) Sliding Door: Specifications as per BOQ	4300	2500	1	495,000	495,000	**Inclusive**	
	Swing Door : Specifications as per BOQ						**Inclusive**	
	Single Leaf door (Size - 1.20 x 2.50M)	1200	2500	1	49,412	49,412	**Inclusive**	
	Double Leaf door (Size - 1.80 / 2.00 x 2.50M)	1800	2500	1	98,824	98,824	**Inclusive**	
				Total		**77,149,288**		
				P&F Charges	3%	2,314,479		
				Total Without Taxes		79,463,767		-
				GST Extra @ 18%	18%	14,303,478.00		-
				Total With Taxes		**93,767,245**		**-**
2				Transportation Charges		Extra at Actual		
3				Unloading Charges @ Site		In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Motorized Sliding Gate	
Door type	**Single Leaf Sliding Gate**
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	**Inside area**
Design Pattern	**Standard Tubular Design Pattern**
Outer Tube	**100 X 50 X 4 mm THK SQ. TUBE**
For Post	**100 X 50 X 4 mm THK SQ. TUBE**
Inner Vertical Flat	**50 X 10 mm FLAT**
Bottom Rail on ground	**Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams**
Bottom Rollers	**Heavy Duty Bottom Wheel With both side Bearings (chorme plated)**
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	**2 Coats of EPOXY polyamide based enamel finish of approved colour**
El motor make	**BFT – Italy (100% imported)**
Emergency Operation	**Manual after turn the switch**
Operating Switch	**Push Button from inside**
Safety	**Photocells, Flashing Light**
Metal Rack	**zinc plated metal rack**

NIHVA Make Dock Leveller





Sr. No.	Description	Specifications
1	Capacity	6 Ton - 15 Ton UDL
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 150 mm
7	Platform Size (W x L)	2250 mm x 2500 mm
8	Lip size (W x L)	2250 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	10%
11	Clear Pit dimensions (W x L x D)	(W) 2300mm x (L)2500 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm^2
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Make High Speed Door



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	Use	Internal Door
2	Control Panel	4 Push Button operated
3	Security Features	EN 13241-1 Standard
4	Resistance to wind load	EN12424 upto class 1
5	Curtain	Fabric Transparent PVC section
6	Guide Material	Aluminum
7	Hood Cover	GI
8	Motor Cover	GI
9	Operator & Control	German Make Motor
10	Connecting Voltage	220V , 1Ph , N
11	Open-Stop-Close Button	Standarad
12	Protection Category	IP 54 / IP 65
13	Power Consumption	0.75 kw Motor
14	Emergency Off Button	Standard
15	Closing Zone Monitoring	Optical Safety edge
16	External Route Monitoring	Photocell
17	Emergency Opening	Crank Handle

G I Motorised Rolling Shutter





Sr. No	Description	Specifications
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 140 mm x 2.5 mm thick
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm
12	Surface finish	Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Direct Drive - German make
14	3 Station Push Button	Included
15	Rubber Bottom Profile	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	**: For High Speed Doors 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.** **: For Dock Levellers, Sliding Gate and other doors 5-6 weeks from the date of receipt of confirmed Purchase order, Advance Payment & Drawing approval**
Payment	: 40% Advance along with Confirmed Purchase Order & Balance 60 % before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd