UNIVERSAL CASE ERECTOR

9th April 2021

OVERVIEW

1. Project Background and Description

Objective is to automate manual case erection and bottom flap closing process executed in various P&G India sites with different

- The pilot for the project will be carried out in the EOL at the Hyderabad plant
- Prime objective is to validate the objective with P&G material and conditions (mentioned in next section) with proof of concept (POC) by May'21 before actual order release. Please note that if POC fails, PO/payment shall not be awarded.
- The target affordable capital (complete scope) < $10M
- Basis affordability and business need, reapplication potential shall be assessed.

2. Project Scope

Basic data:

a. Optimized footprint occupation: 48sqft to 75sqft
b. Minimal changeover time
c. Speed range: 8cpm – 20cpm
d. Box dimensions (approx.):
   Min LBH (mm): 200x200x200
   Max LBH (mm): 570x500x500
e. Should meet other constraints: 3 ply carton thickness suitability, environmental conditions like moisture

3. Requirements

Basis this requirement, request proposal with best fit solution – meeting all the above requirements. The deliverables should include the following:

1. **Overview of models in the below tabular format**

S.No.	Application	Model name	Avg speed (CPM)	Technical info (***please refer #2 below the table***)	Budgetary quotation	Footprint occupied (SQFT)	Attachments (Budgetary quotation, DWG & layout/ technical spec)	Lead time (weeks)	SPOC Contact details
1	Case erector and bottom sealing	*ABC*	*8-10*						
		DEF	*11-15*						
		GHI	*15-20*						

2. Technical info:

a. Min-Max Carton dimensions (mm)

b. Magazine: Horizontal or Vertical, LH or RH

c. Magazine capacity

d. Carton opening mechanism: vacuum or mechanical. If vacuum, type of vacuum system

e. Make/type of electrical control, HMI

f. Safety standards compliance

3. Detailed Budgetary quotation

For queries, Divya Kothapalli (Kothapalli.d@pg.com) - 8179245669