NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HIRANANDANI COMMUNITIES
Mumbai
Maharashtra -India.

Date : 02.03.2020
Quote NO : SQT.19-20_2353R2
Kind Attn : Mr. Vivekanad Kamble
Email Id : vkamble@hrealty.com
Contact No: 7718811540

Project Name & Location: HIRANANDANI PARKS, Chennai

Subject : Quotation for Rolling Shutter , Fire Rated Rolling Shutter, Dock Leveler, High Speed Fold Up dppr

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1A	**MS Motorized Rolling Shutter - Indirect Drive**	7000	8000	8	455,000	3,640,000	Included in supply Prices	
2A	**MS Motorized Rolling Shutter - Indirect Drive**	7000	4000	2	221,000	442,000	Included in supply Prices	
3A	**MS Motorized Rolling Shutter - Indirect Drive**	2450	3000	9	82,000	738,000	Included in supply Prices	
1B	**MS Motorized Rolling Shutter - Direct Drive**	7000	8000	8	625,000	5,000,000	Included in supply Prices	
2B	**MS Motorized Rolling Shutter - Direct Drive**	7000	4000	2	397,000	794,000	Included in supply Prices	
3B	**MS Motorized Rolling Shutter - Direct Drive**	2450	3000	9	134,000	1,206,000	Included in supply Prices	
4	**Fire Rated Rolling Shutter**	7500	5000	2	502,000	1,004,000	Included in supply Prices	
5	**Fire Rated Rolling Shutter**	7000	8000	4	728,000	2,912,000	Included in supply Prices	
6	**Fire Rated Rolling Shutter**	6000	7000	4	532,000	2,128,000	Included in supply Prices	
7	**Fire Rated Rolling Shutter**	3500	4000	4	274,000	1,096,000	Included in supply Prices	
8	**High Speed Fold up door**	7500	5000	2	575,000	1,150,000	Included in supply Prices	
9	**High Speed Fold up door**	7000	8000	4	740,000	2,960,000	Included in supply Prices	
10	**High Speed Fold up door**	6000	7000	4	599,000	2,396,000	Included in supply Prices	
11	**High Speed Fold up door**	3500	4000	4	272,000	1,088,000	Included in supply Prices	
12	**Dock Leveller - 9 ton**	2200	3000	6	200,000	1,200,000	Included in supply Prices	
13	**Dock Leveler - 20 Ton**	2200	3000	1	225,000	225,000	Included in supply Prices	
	Total - (1A+2A+3A+4+5+6+7+8+9+10+11+12+13)					**20,979,000**		-
	P&F Charges			Nil				
	Total Without Taxes					**20,979,000**		**-**
	GST Extra @ 18%			18%		3,776,220		
	Total With Taxes					**24,755,220**		**-**
	Transportation Charges					**In NIHVA SCOPE**		
	Unloading Charges @ Site					**In NIHVA SCOPE**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Rolling Shutter

Sr. No	**Specification**	**MS Motorized Rolling Shutter**
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S.Wind lock Guide profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	**Option 1 :-** Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection **Option 2:**- Electric Motor - Direct Mounting

Fire Rated Rolling Shutter

Sr .No.	**Description**	**Specification**
1	Rolling Shutter	Fire Rated Rolling Shutter
2	Shutter Slats	Zinc Coated Steel Solid Slats
3	Slat Thickness	1.00 mm
4	Shutter Guide	Galvanise Steel
5	Bottom Bar	SKB - T120
6	Fire mode	Fire Shutter will autoclose via 71 degree C Thermal Fuisable Link Fire shutter will auto close by gravitywhen recived 24V DC fire signal from control room
7	Operated By	Motorise 230volt 50Hz 1P with Manual override chain

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA High Speed Fold Up Door

Sr. No	**Specification**	**NIHVA Make High Speed Fold Up Door**
1	Use	Internal Door
2	**Control Panel**	4 Push Button operated
3	Curtain	PVC Canvas
4	Guide Material	Powder Coated
5	Hood Cover	GI Powder Coated
6	Motor Cover	GI Powder Coated
7	Operator & Control	German Make Motor
8	Open-Stop-Close Button	Standarad
9	Emergency Off Button	Standarad

NIHVA Dock Leveler

Sr. No	Description	Specifications For 9 Ton	Specifications For 20 Ton
2	Make	NIHVA	NIHVA
3	Required Capacity	9 Ton	20 Ton
4	Hydraulic Power pack	1 HP, 3PH	1 HP, 3PH
5	Control Panel	4 Push Button operated	4 Push Button operated
6	Deck operation	By push button Deck UP & Deck Down	By push button Deck UP & Deck Down
7	Lip operation	By push button Deck UP & Deck Down	By push button Deck UP & Deck Down
8	Loading platform height from road Level	4 feet (1200 mm)	4 feet (1200 mm)
9	Travel above from Dock level height	350 mm	350 mm
10	Travel below from Dock level height	200 mm	200 mm
11	Deck platform size	2200mm (W) x 3000mm (L) x 600mm (H)	2200mm (W) x 3000mm (L) x 600mm (H)
12	Lip sizes	400 mm	400 mm
13	Clear Pit dimensions	2240mm (W) x 3000mm (L) x 605mm (H)	2240mm (W) x 3000mm (L) x 605mm (H)
14	Drive type	Direct by electric Motor	Direct by electric Motor
15	Power Consumption	0.75 kw Motor	0.75 kw Motor
16	Degree of protection for motor	IP 55	IP 55
17	Motor RPM	1410 rpm	1410 rpm
18	Pump design flow	1.8 LPM	1.8 LPM
19	Pump pressure	200 bar	200 bar
20	Safety valve set pressure	90 bar	90 bar
21	Pump type	Gear	Gear
22	In built safety valve	Yes	Yes
23	Volume of oil receiver	8 Ltr	8 Ltr
24	No of Deck Cylinders	2 Nos	2 Nos
25	Deck Plate Thickness	8 mm Chequered Plate	8 mm Chequered Plate
25	No of Lip Cylinders	1 No	1 No
25	Lip Plate	16 mm Thick Plate	16 mm Thick Plate
26	Dock Bumpers	1 Pair included	1 Pair included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	NIHVA Scope
4	All structure support required	In Client Scope
5	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
6	Conduits, Cables required	NIHVA Scope

D) Terms & Conditions

Price : Ex Works Site

Delivery : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd