NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ion Exchange (India) Ltd.
ION House, Dr. E. Moses Road, Mahalaxmi, Mumbai-400 011, India.

Date : 03.02.2021
Quote NO : SQT.20.21.2994
Kind Attn : Bindiya Chavda
Email Id : bindiya.chavda@ionexchange.co.in
Contact No: 98 9212 2553

Subject : Quotation for Motorized Single Leaf Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Single Leaf Sliding Gate	4500	1800	1	320,000	320,000	20,000	20,000
				Total		**320,000**		**20,000**
2			P&F Charges	3%		9,600		
			Total Without Taxes			329,600		20,000
			GST Extra @ 18%	18%		59,328.00		3,600
			Total With Taxes			**388,928**		**23,600**
3			Transportation Charges			Extra at actual		
4			Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate as per Drawing
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	80X80X4 MM THK SQ. TUBE
6	For Post	80X80X4 MM THK SQ. TUBE
7	Innear Tube	40 X 40 X 3.2 MM THK SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light
17	Operation	By Telescopic Mechanism
18	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4. Hooter
		5. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd