NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Address
Air Works India (Engineering) Pvt. Ltd
Kochin

Date : 11.01.2020
Quote NO : SQT.19.20.2326
Kind Attn : Mr. K.Parameswaran Namboodiri
Email Id : kp.namboodiri@airworks.in
Contact No: 9910770210

Project Name & Location: Take up Conveyor with semi automatic loading and unloading of passenger seat assembly: Kochin

Subject : Quotation for Take up Conveyor with semi automatic loading and unloading of passenger seat assembly

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Take up Conveyor with semi automatic loading and unloading of passenger seat assembly	7500	850	1	11,90,000	11,90,000	1,25,000	1,25,000
				Total		**11,90,000**		**1,25,000**
2	P&F Charges			3%		**35,700**		
	Total Without Taxes					**12,25,700**		**1,25,000**
	GST Extra @ 18%			18%		2,20,626		22,500
	Total With Taxes					**14,46,326**		**1,47,500**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

B) Technical Specification

Description	Specification
Length :	7500 mm
Width	850 mm
Take up loading height	100 mm
Take up Discharge height	3600 mm
Speed	10 mtr/ min
Opeartion mode	Manual (inching type from operating pendant
Safety railing at unloading height of conveyor system	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8- 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shailendra Saindane on 7709209333**

With Best Regards

Yogita

8530872333

For NIHVA Technologies Pvt Ltd