NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Smith Structures India Pvt. Ltd.
Ahmedabad

Date : 03.03.2021
Quote NO : SQT.20.21.3071
Kind Attn : Atul Patil
Email Id : atul@smithstructure.com
Contact No: 9860798510

Project Name & Location: Atul Ltd Valsad

Subject : Quotation for GI Motorised & Gear Operated Rolling Shutter .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**GI Motorised Rolling Shutter**	3000	3000	4	86,000	344,000	20,000	80,000
2	**GI Gear Operated Rolling Shutter**	3000	3000	4	65,000	260,000	20,000	80,000
				Total		**604,000**		**160,000**
	P&F Charges on Total Supply Value			3%		**18,120**		
	Total Without Taxes					**622,120**		**160,000**
	GST Extra @ 18%			18%		111,981.60		28,800
	Total With Taxes					**734,102**		**188,800**
	Transportation Charges					**Inclusive**		
	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorised Rolling Shutter





Sr. No	Description	Specifications
1	**Rolling Shutter**	Rolling Shutter with GI slat of thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Curtain Panel**	The panel made of 1 mm thick GI slat
4	**Curtain panel size**	75mm wide
5	**Curtain Profile**	Curved with perforation at 0.5 mtr
6	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GI
11	**Surface finish**	Powder coated
12	**Drive Unit & Mounting Type**	Electic motor - In direct Mounting - IP 54

Gear Operated Rolling Shutter

Sr. No	Description	Specifications
1	**Rolling Shutter**	Rolling Shutter with GI slat of thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Curtain Panel**	The panel made of 1 mm thick GI slat
4	**Curtain panel size**	75mm wide
5	**Curtain Profile**	Curved with perforation at 0.5 mtr
6	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GI
11	**Surface finish**	Powder coated
12	**Drive Unit & Mounting Type**	Gear Assembly

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : FOR Site Delivery

Delivery : 5 - 6 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bhavin Jain on 8551092333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd