NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

MMC Doortech
Chennai

Date : 22.01.2021
Quote NO : SQT.20.21.2963
Kind Attn : Miss. Mahalasmi R
Email Id : jollybanerji@gmail.com
Contact No: 9884082122

Project Name & Location: Microsoft Project

Subject : Quotation for 2 Hrs Double Wall Fire Rated Insulated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**2 Hrs Fire Rated Double Wall Insulated Shutter**	9600	4000	2	1,313,000	2,626,000	20,000	40,000
2	**2 Hrs Fire Rated Double Wall Insulated Shutter**	4000	4000	2	614,000	1,228,000	15,000	30,000
3	**2 Hrs Fire Rated Double Wall Insulated Shutter**	3000	3000	1	398,000	398,000	15,000	15,000
4	**2 Hrs Fire Rated Double Wall Insulated Shutter**	2800	2400	1	322,000	322,000	15,000	15,000
			Total Value			**4,574,000**		**100,000**
			P&F Charges	3%		137,220		
			Total Without Taxes			**4,711,220**		**100,000**
			GST Extra @ 18%	18%		848,020		18,000
			Total With Taxes			**5,559,240**		**118,000**
			Total (Supply + Installtion) with Taxes					**5,677,240**
4			Transportation Charges			**Extra at Actual**		
5			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: SKB-F7D Double Walled Roll Form Steel with Rockwool Infilled**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Extruded Aluminium G70**
- **Operated by: Motor with one unit push button switch & manual override**

Fire Rated Rolling Shutter

Sr .No.	Specification	Fire Rated Rolling Shutter - SKB BS 476
1	**Shutter Curtain**	SKB-F7D Double Walled Roll Form Steel with Rockwool Infilled
2	**Guide Rail**	Powder coated
3	**Bottom Bar**	Powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 230v 50Hz 1 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
6	**Standard RAL colors:**	RAL 9002
7	**Protection Category**	BS 476

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 9-10 weeks for Fire rated shutters from the date of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 85510198333.**

With Best Regards
Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd