NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1522 **Date : 26.04.2019**

Kaizen Airtech Solutions
Narhe
Pune
Maharastra, India

Kind Attn: **Mr. Yuvraj Shelke**
Email: info@kaizenairtech.com
Contact No: 7620446570

Project Name And Location :

Subject: Quotation for High Speed Door HS9020GHY

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
Option 1	**ASSA ABLOY Make Rapid Roll Up Door HS9020G** **(Supply + Installation)**				
Operating speed	Opening: up to 1,2 m/s 2, closing: 0,5 m/s .The fast opening and closing speed improves your traffic flow, provides employee comfort, and saves energy.				
Wind load resistance,	Class 1 (300 N/m2), maximum wind load while closing 50 N/m2				
Techncial details	a. The soft bottom edge has no rigid parts, it moulds around any obstruction to prevent injury or damage. b. When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side guides without causing damage or being damaged itself. c. Vision Window - One row of 400 mm height				
1	**Size:(W) 3000 mm x (H) 3000 mm**	3	No	555,000.00	1,665,000.00
Option 2	**ASSA ABLOY Make Rapid Roll Up Door HS9020GHY** **(Supply + Installation)**				
Area of use:	Inside, in humid/corrosive and hygiene environments				
Material:	Construction in stainless steel AISI304				
Colours:	8 standard colors - white, yellow, green, orange, red, gray, black, blue				
Safety:	1) Photocells in side columns 2) Flexible soft bottom edge including wireless edge activator 3) Break-away and self-repair function				
Vision Window	Single row with 400 mm Height				
Operating speed:	Opening: up to 1,2 m/s (optional 2,0 m/s) Closing: 0,5 m/s				
Wind load resistance:	Class 1 (300 Pa (N/m^2)) maximum wind load while closing 50 Pa (N/m^2)				
Water penetration:	Class 2 (50 Pa (N/m^2))				
Air permeability:	Class 1 (24 $m^3/m^2/h$ at 50 Pa)				
Thermal transmittance:	6,02 $W/(m^2K)$				
Lifetime expectations:	1.000.000 cycles				
Temperature working range:	5 °C to +40 °C				
1	**Size:(W) 3000 mm x (H) 3000 mm**	3	No	663,000.00	1,989,000.00
B	**ASSA ABLOY Automatic Sliding Door SL 500** **Supply + Installation**				
1	Size: (W) 1524 mm x (H) 2134 mm	1	No	195000	195000

GST Pune :	27AAECN0437H1ZM

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
C	**Non Fire rated Door with Rockwool Infill .GI Sheet Doors panel with 46mm thk & 0.8 mm Face Sheet.Frame 1.2mm thk. and 100X57mm Jamb depth & width**				
1	**Single Leaf Door Size : (W) 1100 mm x (H) 2100 mm**	7	No's	15,900	111,300
Specifications	SS Ball Bearing Hinge 102X76X3mm Dorma -BB3090F	28	No's	600	16,800
	Vision Panel			3,100	
	Door Closer - TS 68 (66400101)	7	No's	3,100	21,700
	Anchor Fastener	70	No's	200	14,000
	External Trim	7	No's	5,800	40,600
	Panic Bar (Single Point)	7	No's	7,100	49,700
	Installation Charges	7	No's	6,500	45,500
				Total	**299,600**
D	**Double Leaf Door Size : (W) 1500 mm x (H) 2100 mm**	4	No's	19,800	79,200
Specifications	SS Ball Bearing Hinge 102X76X3mm Dorma -BB3090F	32	No's	600	19,200
	Vision Panel – 200 x 300 mm	8	No's	3,100	24,800
	Door Closer - TS 68 (66400101)	8	No's	3,100	24,800
	Anchor Fastener	52	No's	200	10,400
	External Trim	4	No's	5,800	23,200
	Panic Bar (Single Point)	4	No's	7,100	28,400
	Panic Bar (Double Point	4	No's	10,500	42,000
	Flush Bolt	8	No's	1,100	8,800
	Installation Charges	4	No's	6,500	26,000
				Total	**286,800**

Client Scope of Work:

1. Custom Duty + Custom Clearance + Local Transport, till site in clients Scope. NIHVA will handover BL to client for further all process & action till material reaches at site & unloads at required place.
2. For High Sea sale responsibility of NIHVA ceases on transfer of BL to client.
3. Client should issue required forms to NIHVA for all Tax Exemptions.

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	@3 % of total supply value
3	**Delivery**	:	10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
4	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch
5	**Insurance**	:	Extra As applicable
6	**Tax**	:	GST @ 18%
7	**Validity**	:	Validity of Offer is 15 days from the date of quotation
8	**Warranty**	:	12 months from the date of supply

For any queries please feel free to contact Mr. Arjun Patil 8551096333

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd