NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Date : 27.06.2020
Quote NO : SQT.20.21.04
Kind Attn : Ms. Pooja
Email Id : pip.ipl.pune@gmail.com
Contact No : (020)-27143067

Progressive Infra Project India Pvt. Ltd.
Office address: 31/1, Sai Niketan, In front of
Mega mart, old Mumbai-Pune Highway,
Dapodi, Pune-411012.

Project Name & Location: Tasty Bytes

Subject : Quotation for Rolling Shutter, High Speed Door , Sectional Door and Dock Leveller and Dock Shelter .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**GI Motorised Rolling Shutter + Structure**	4000	4000	1	2,96,000	2,96,000	20,000	20,000
1	**GI Motorised Rolling Shutter + Structure**	4000	5000	1	3,15,000	3,15,000	20,000	20,000
2	**Double Wall Motorised Rolling Shutter**	4000	4000	1	4,11,000	4,11,000	20,000	20,000
	Double Wall Motorised Rolling Shutter	4000	5000	1	4,47,000	4,47,000	20,000	20,000
3	**High Speed Door HS9020G + Structure**	3000	3000	1	6,20,000	6,20,000	20,000	20,000
4	**Sectional Door + Structure**	3000	3000	1	3,63,000	3,63,000	20,000	20,000
5	**Nihva Make Dock Leveller**	2200	2500	1	2,70,000	2,70,000	20,000	20,000
6	**Dock Shelter**	3400	4500	1	2,74,000	2,74,000	20,000	20,000
				Total		**29,96,000**		**1,60,000**
7	P&F Charges			3%		**89,880**		
	Total Without Taxes					**30,85,880**		**1,60,000**
	GST Extra @ 18%			18%		5,55,458		28,800
	Total With Taxes					**36,41,338**		**1,88,800**
8	Transportation Charges					**In Client Scope**		
9	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1.Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Direct Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection

2.Double wall Rolling Shutter

Sr .No.	Specification	Double Wall Rolling Shutter
1	Mounting Surface	Side Brackets: Optional = On Concrete / Steel & Side Guides : Optional = On Concrete/Steel / Masonry
2	Opening/Closing Speed	0.1 m/sec
3	Slat size	95mm x 19mm with PU filled inside
4	Bottom Profile	125mm x 15mm with extra angle support. (Optional - Rubber Bottom Seal)
5	Side Guide Profile	M.S." U" Shaped profile 125 x 40mm x 3 mm thick (as per the opening width dimension)
6	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia - 100 to 300 mm as per w x h
7	Side Brackets	MS Plate 3 mm to 10 mm thick , as per the opening dimension
8	Hood Cover	Made of GI Sheet Thickness 0.8 mm with 25x25x3mm angle stiffener
9	Painting	Powder coated – Off white color
10	Control Type	Optional = Dead man / Pulse Control
11	Drive Unit & Mounting Type	Electric Motor (Imported German Make) (Single Phase/Three Phase) - Direct Mounting on
12	Emergency Operation	Option = Manual Hand Driven / Chain Wheel Drive

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

3 .High Speed Door

Sr. No	Description	Specifications
1	Structure	Galvanized steel
2	Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	Safety	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	Operation	Operator + control unit
5	Operating speed	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	Wind load resistance	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
7	Air permeability	Class 1 (24 m³/m²/h at 50 Pa)
8	Water penetration	Class 2 (50 Pa (N/m²))
9	Thermal transmittance	6,02 W/(m²K)
10	Lifetime expectations	1.000.000 cycles
11	Temperature working range	5 °C to +40 °C
12	Vision window	Horizontal one row of height 400 mm at eye level

4 .Sectional Door

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	Door Model	1042P	
2	Door produced Based on which certificatio	Doors produced according to ISO 9000 or ISO 14000 certified	
3	Opening/Closing Speed	0.25 m/s	
4	Door Material	GI Steel with PUF inside	
5	Panel Thickness	42mm	
6	Panel colour	RAL 9002 Powder coated	
7	External surface of the panel	diamond grid design with a glossy finish at the section joints.	
8	inside surface of the panel	Monolithic surface on the inside of the door	
9	Broken cold bridge	Section joints with broken cold bridges	
10	Door sealent	All door sealants made of EPDM rubber.	
11	All Panel height	All panels should be 545mm high	
12	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.	
13	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.	
14	Steel component Material	All steel components to be electro galvanized	
15	Hinge Material	Glass fibre reinforced Polyamide	
16	Panel Thickness	42 mm	
17	Spring Material surface finish	Powder coated	
18	Water Penetration	EN 12425	class 3
19	Air Permealibity	EN12426	class 2
20	Wind Load	EN21424	class 3
21	Thermal Transittance	EN 12428 1.10W /m2K	
22	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
23	Door saftey device 1	Doors equiped with spring break device	
24	Interlocking with High Speed Door	Included	
25	Door saftey device 2	Door equiped with pneumatic safety edge	
26	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

5 .Nihva Make Dock Leveller

Sr .No.	Description	Specifications
1	Capacity	3.5 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2200 mm x 2500 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Overall length	2200mm x 2500mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 2550 mm x (D)480 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Structure	Included
24	Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil structural work required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 -11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333 .**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd