NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JMC Projects (India) Limited
(A Kalpataru Group Company)
Kalpataru Synergy, Opp. Hotel Grand Hyatt
Santacruz (E), Mumbai 400 055

Date : 18.01.2021
Quote NO : SQT.20.21.2954
Kind Attn : Mr. Muzaffar Madni
Email Id : Muzaffar.Madni@jmcprojects.com
Contact No: 8291349534/9022425678

Project Name & Location MMRCL _ Girgaon

Subject : Quotation for Push-Pull Rolling Shutter ,Perforated Rolling Shutter and MS Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Push-Pull Rolling Shutter - GI Laths**	3000	4000	1	72,000	72,000	20,000	20,000
2	**Push-Pull Rolling Shutter - GI Laths**	3500	4000	1	81,000	81,000	20,000	20,000
3	**Push-Pull Rolling Shutter - GI Laths**	3500	4500	1	90,000	90,000	20,000	20,000
4	**Perforated Push-Pull Rolling Shutter - GI Laths**	3000	4000	1	85,000	85,000	20,000	20,000
5	**Perforated Push-Pull Rolling Shutter - GI Laths**	3500	4000	1	94,000	94,000	20,000	20,000
6	**Perforated Push-Pull Rolling Shutter - GI Laths**	3500	4500	1	103,000	103,000	20,000	20,000
7	**MS Motorised Single Leaf Sliding gate**	12000	1800	1	409,000	409,000	20,000	20,000
8	**MS Motorised Double Leaf Sliding gate**	12000	1800	1	437,000	437,000	20,000	20,000
	Total			**8**		**1,371,000**		**160,000**
9	P&F Charges			3%		41,130		
	Total Without Taxes					**1,412,130**		**160,000**
	GST Extra @ 18%			18%		254,183		28,800
	Total With Taxes					**1,666,313**		**188,800**
10	Transportation Charges					**Extra at Actual**		
11	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Push Pull Manual Rolling Shutter

Sr .No.	Specification	GI Push Pull Operated Rolling Shutter
1	Description:	Push Pull Operated Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc
12	Operation	Push Pull

Perforated Push Pull Manual Rolling Shutter

Sr .No.	Specification	GI Push Pull Operated Rolling Shutter
1	Description:	Push Pull Operated Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved - Perforated
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc
12	Operation	Push Pull

Motorized Single Leaf & Double Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf & Double Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Gate Size	(W) 12000 MM x (H) 1800 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Tube	72 x 72 x 3.2mm MS SQ. TUBE
7	For Post	72 x 72 x 3.2mm MS SQ. TUBE
8	Innear Tube	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
9	Gap Between Tubes	125mm
10	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
11	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
12	Guide Rollers supporter during Gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement
13	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
14	El motor make	BFT – Italy (100% imported)
15	Emergency Operation	Manual after turn the switch
16	Operating Switch	Push Button from inside
17	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Work Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards

Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd