NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ethics Infotech LLP
Vadodara

Date : 03.03.2022
Quote NO : **MHE_21.22.0060**
Kind Attn : Mr. Mayur Gajera
Email Id : mayur.gajera@ethicsinfotech.in
Contact No: 9157708175

Project Name & Location: Ethics Infotech LLP Vadodara

Subject : Quotation for Telescopic Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Belt Conveyor** • Total Length- 11mtr (Fixed-5mtr, Extended-6mtr) • Capacity- 50boxes/hour • Belt Width - 600 mm	1	14,20,000	14,20,000	75,000	75,000
	TOTAL EXCLUDING TAXES			14,20,000		75,000
2	GST Extra @ 18%	18%				Extra At Actual
3	P&F Charges	3%				Extra At Actual
4	Transportation Charges					Extra At Actual
5	Insurance Charges					Extra At Actual
6	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Boxes
2	Size of boxes	400 X 400 X 500mm
3	Weight of bags	30 Kg
4	Capacity	50 boxes/hr
5	Belt Width	600 mm
6	Belt Type	2 Ply 3.2 mm PVC
7	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
8	Length Of Conveyor	Fixed Length : 5000 mm Telescopic (Expanded) : 6000 mm Total Length : 11000 mm
9	Main Body Of Conveyor	MS Powder coated
10	Direction	Both Forward and Reverse direction
11	Working height	Min.850 mm and max. 1100 mm
12	Inclination Height	Max. 1200 mm
13	Speed adjustment	VFD (Schneider /Allen Bradley/Delta)
14	Gear Box	Bonfiglioli
15	Driven Motor Make	Bonfiglioli /CG/BBL , IE2
16	Movement	Wheel for easy movability

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd