NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ALDECOR INTERIORS PVT LTD.
39/2(O), KALYANI GARDEN, GANGAMMA TEMPLE STREET,
ASHOK NAGAR, BSK 1ST STAGE, BANGALORE - 560050.

Date : 16.12.2019
Quote NO : SQT/19-20/2157R6
Kind Attn : Deepa
Email Id : deepa@aldecorindia.com
Contact No: 9980956528

Subject : Quotation for Flap Barrier .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Double Sided Flap Gate	1	116000	116,000	Included In Supply	
2	Single Sided Flap Gate	2	88000	176,000	Included In Supply	
3	Biomatric + Card Based Reader	4	7000	28,000		-
4	Biomatric + Card Based Reader USB Base Reader for Enrollment Process	1	8000	8,000		-
5	Network Cable Acces Control System	1	23000	23,000		-
6	Blank RFID Cards	500	20	10,000		-
7	SMPS Power Supply for Access Control System.	1	2000	2,000		-
		Total		**363,000**		**-**
6	P&F Charges	3%		NIL		
	Total Without Taxes			363,000		-
	(Supply + Installation)			**400,000**		
	GST Extra @ 18%	18%		72,000		-
	Total With Taxes			**435,000**		**-**
7	Transportation Charges			Included		
8	Unloading Charges @ Site			In Client Scope		

Su

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Double Sided Flap Gate :

• It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseding, it will stop working automatically in certain time, and the potency is small, will make an alarm sound at the same time. • Reseng automatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. •High throughput, Bi-directional control, Open / Close light indication •Optical beams for safety movements, Ensures rapid, efficient & safe access control • Easily integrated into access control system, Automatic reset of barrier flap after each valid entry, mechanical release key for emergency cases, fire trigger input facility. In the even of power failure panels can be specified to remain closed• The whole system works steadily, and the noise is very low. Size: 1400 x 280 x 980mm; Unlock time: 0.2s Pass rate: 35 person/min; Pass Width: ≤550mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -25~70°c; Power Consumption: 35w; Input: 12v dry contact.

Single Sided Flap Gate:

• It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in resending, it will stop working automatically in certain time, and the potency is small, will make an alarm sound at the same time. • Reseng automatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. •High throughput, Bi-directional control, Open / Close light indication •Optical beams for safety movements, Ensures rapid, efficient & safe access control • Easily integrated into access control system, Automatic reset of barrier flap after each valid entry, mechanical release key for emergency cases, fire trigger input facility. In the even of power failure panels can be specified to remain closed• The whole system works steadily, and the noise is very low. Size: 1400 x 280 x 980mm; Unlock time: 0.2s Pass rate: 35 person/min; Pass Width: ≤550mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -25~70°c; Power Consumption: 35w.

Networkable Access Control System:

Fingerprint Capacity : 3000 Templates; Transaction Capacity : 30,000 Transacations; Sensor : Optical Sensor; Algorithm Version : Finger V9.0&10.0; Communication : Rs232/485, TCP/IP, USB-HostWiegand Signal : Input & Output; Interface Styles : Common, Matrix and Magic Styles; Standard Funcation : Webserver, Anti-PassbackDisplay : TFT LCD Color Screen

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat on7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd