OZONE LIFT

Lift Quotation

QT No :-	QT-OL-PR-KS-03-2020-185
Date :-	4-Mar-2020
Client Name :-	M/s Nihva Technologies Pvt. Ltd.
Site Name :-	-
Site Address :-	187, G-Block, 1st Floor, Thermax Sqaure, Above Renault Showroom, Chinchwad, Pune-411019 (MH).
Sales Engineer :-	Mr. Yogesh Mahatme
Designation :-	Manager (Sales Department)

QT No :- QT-OL-PR-KS-03-2020-185

Date :- 4-Mar-2020

To,

Client Name :- M/s Nihva Technologies Pvt. Ltd.

Site Name :- -

Site Address :- 187, G-Block, 1st Floor, Thermax Sqaure, Above Renault Showroom, Chinchwad, Pune-411019 (MH).

Dear Sir,

Subject :- Supply, Installation, Testing and commissioning of Lift for your esteemed project.

As desired by you, we have pleased to submit our offer for supply & installation of OZONE LIFT for your building at above address, which is subject to enclosed specifications.

We hope that you will find our offer most competitive & favor us with your valuable order. We assure you will receive our best attention & services at all times.

We look forward to work with you.

Thanking You.

Yours Truly,
OZONE LIFT,
Mr. Sandip Shisode
Managing Director
Mobile No. - 7721903334
www.ozonelift.com

OZONE LIFT

LIFT SPECIFICATION :-

Sr. No.	DESCRIPTION	SPECIFICATIONS
I. MAIN LIFT SPECITIONS -		
1	NO.OF LIFT	1
2	TYPE OF ELEVATOR - APPLICATION	Goods
3	TYPE OF MACHINE & LOCATION	Geared With Machine Room
4	CAPACITY	1 Ton
5	RATED LOAD IN KG	1000
6	RATED SPEED IN - m/s	0.50
7	ROPING	2:1
8	POWER SUPPLY	3 Phase, 415 Volts, 50 Hz
9	CONTROL	Simplex Down Collective Control
10	DRIVE	V3F Drive (Variable Voltage Variable Frequency)
11	FLOOR	G+1
12	ENTRANCE POSITION	Same Side
13	NOS. OF STOPS	2
14	NOS. OF OPENINGS	2
15	SHAFT SIZE - W (mm) X D (mm)	2650 x 1950
16	HEAD ROOM HEIGHT (mm)	4500
17	PIT DEPTH (mm)	1600
18	TRAVEL (mm)	5000

19	CABIN SIZE	
i	CABIN WIDTH (mm)	1500
ii	CABIN DEPTH (mm)	1600
II. LIFT DOOR SPECITIONS -		
20	DOOR OPERATION	Manual
21	DOOR OPENING (WIDTH x DEPTH)	1500 W x 2000 H
22	TYPE OF CAR DOOR	Manual Collapsible Door
23	TYPE OF LANDING DOOR	Manual Collapsible Door
24	CAR DOOR FINISH	MS Powder Coated Finish
25	LANDING DOOR FINISH	MS Powder Coated Finish
III. LIFT CABIN SPECITIONS -		
26	CABIN WIDTH (mm)	1500
27	CABIN DEPTH (mm)	1600
28	CABIN ENCLOSER (FINISH)	MS Powder Coated Finish
29	SPECIAL CABIN (STRIP OR DESIGNER)	Not Required
30	CABIN FLASE CEILING	Decorative OL-LED Spot Light
31	CABIN FLOORING	Aluminium Cheq. Plate (3mm)
32	CABIN VENTILATION	Fan
33	HANDRAIL - ROUND SSHL FINISH	Yes
34	STAINLESS STEEL MIRROR PANEL	No
IV. CAR AND LANDING OPERATING PANEL DISPLAY SPECITIONS -		
35	COP & LOP TYPE	HALF LEGTH_SSHL_BOX TPES
36	DISPLAY	Seven Segment
37	Push Button Type / Touch Screen	Push Button Type

V. OTHERS FEATURES -	
38	**ARD (Auto Rescue Device) system** - In case of power failure, ARD system gets cabin to the nearest landing floor so that passengers can safely come out.
39	Voice announcement system.
40	Auto circuit for Cabin lights and fan.
41	Digital position indicator in car & at all floors.
42	Up/Down direction indicators in car & at all floors.
43	Battery operated alarm bell.
44	Door open bell.
45	
46	
47	
48	
49	
50	

OZONE LIFT

TECHNICAL SPECIFICATION :-

Sr. No.	NAME OF COMPONENTS	MAKE
1	TRACTION MACHINE	MONTANARI (ITALY)/EQUIVALENT
2	SPEED GOVERNER	MONTANARI (ITALY)/EQUIVALENT
3	GUIDE RAILS	SAVERA (SPAIN)
4	DOOR	OZONE LIFT (INDIA)
5	ROPE	USHA MARTIN (INDIA)
6	DRIVE	MONARCH (CHINA)
7	CONTROL PANEL	MONARCH (CHINA)
8	CABELS (ELEVATOR HARNESS)	POLYCAB (INDIA)
9	CABIN & STRUCTURAL COMPONENTS	OZONE LIFT (INDIA)

PRICE :-

Price for supply and installation of **one** number lift, as per given in our enclosed specification page.

1	**ELEVATOR PRICE :-** **(EXCLUSIVE ALL TAX)**	**₹ 850,000**
2	**GST = 18%**	**₹ 153,000**
3	**TOTAL ELEVATOR PRICE :-** **(INCLUSIVE ALL TAX)**	**₹ 1,003,000**

I. All cheques / drafts must be drawn in favor of PUNE REGION - **"OZONE LIFT"**.

II. All cheques / drafts must be drawn in favor of VIDARBHA REGION - **"OZONE LIFTS"**.

Goods and Services Tax (GST)-

Contract prices are inclusive of GST, which is included @ 18.00% on material Value and Erection & Commissioning Charges. Any variation in the above tax structure shall be collected on actual basis at the time of billing.

Note - This Price value valid for 1 year.

ACCEPTED BY,

M/s Nihva Technologies Pvt. Ltd.

-

187, G-Block, 1st Floor, Thermax Sqaure, Above Renault Showroom, Chinchwad, Pune-411019 (MH).

FOR OZONE LIFT,

Mr. Yogesh Mahatme

Manager (Sales Department)

Kalewadi, Pimpri, Pune (MH).

OZONE LIFT

COMPLETION PERIOD :-

• 25 Days for manufacturing & 25 Days for erection & commissioning.

Total completion period required 50 days.

FREE MAINTENANCE :-

• Free maintenance for 12 Month after hand over the Lift.

SCOPE OF WORK :-

I. OZONE LIFT SCOPE :-

• 1 Year comprehensive warranty from date of lift trail.

• Supply, Installation, Testing & Commissioning of the Elevator as per specification agreed.

II. CUSTOMER SCOPE (Civil Work) :-

• Minor Civil Works required for elevator installation.

• Scaffolding in elevator shaft required for elevator installation.

• Landing Entrance Work on each Landing as per OZONE requirement.

• Extra Steel if required suiting the site conditions.

• Complete Construction of Lift Well and machine room as per OZONE requirement.

• Plaster Finish in Lift Well and Machine Room.

• Pit Construction and Water Proofing as per OZONE requirement.

• Minor Builder work such as pocket cutting,Repairing,Drilling in concrete wall.

• Construction of RCC Buffer blocks in Pit.

• Floor Level Marking on each floor.

• Whitewash in Litwell and machine room.

• Wooden Scaffolding as per OZONE requirement.

• Tube light and Exhaust fan with louvers for proper Lighting and ventilation in M/C room.

III. CUSTOMER SCOPE (Electrical Requirement in lift well & machine room) :-

• 4 Core 6 Sq.mm Armored Copper Cable for 3Ø Power Supply in M/C room.

• 2 Core 2.5 Sq.mm Armored Copper Cable for 1Ø Supply in M/C room.

• 8 SWG Copper Earthings from earth pit to Machine room terminating at Earthings Strip in M/C room.

• 63 A/300MA ELCB (4 Pole) For 3Ø -1 No. in Machine Room.

• 16 A MCB (2 Pole) For 1Ø 2 Nos. in Machine Room.

• Bulkhead Fittings with 3 Pin Power Sockets (16A) with ON-OFF Switch each at 1 m from Pit and rest at 2 m Height up to Headroom slab in lift well.

• Tube Light and Ventilation Exhaust fan for Proper Lighting & Ventilation in M/C room.

• Metallic Glands and Lugs for cable Entry in Mains for 3Ø / 1Ø Power Supply.

• Above all materials to be provided and fixed by client.

TERMS & CONDITIONS :-

• The order once placed will not be cancelled in any case.

• The advances payment will not be refundable in any case.

• Physical and water damage not cover under warranty.

• Lift license (Client Scope Documents) submit after signed agreement within 5 working days.

• If any deviation observe in Lift license documents (Client Scope Documents) then only client will be responsible.

PAYMENT TERMS :-

• 20% - Advance against order booked.

• 60% - 30 Days before manufacturing start.

• 15% - Physical completion.

• 5% - Elevator trail.

ACCEPTED BY,

M/s Nihva Technologies Pvt. Ltd.

-

187, G-Block, 1st Floor, Thermax Sqaure, Above Renault Showroom, Chinchwad, Pune-411019 (MH).

FOR OZONE LIFT,

Mr. Yogesh Mahatme

Manager (Sales Department)

Kalewadi, Pimpri, Pune (MH).

Thank you very much…

Waiting for your valuable order…