ATHANG SAFETY & ENGINEERING SOLUTIONS

I-104, ASHWINI CO. OP . HSG. SOC., SHREE SWAMI SAMARTH NAGAR,
CHAKAN ROAD, TALEGAON DABHADE, TAL-MAVAL, PUNE-410507
M: +91-8446522506 | E: athangses@gmail.com
GST No.: 27BRLPK2289L1Z4

QUOTATION

REF. No.: 2021-22/NTPL-001 **Date:** 01-02-2022

Customer: NIHVA Technologies Pvt. Ltd.
Address: Plot No. 187, 1st Floor, G-Block, Thermax Chowk, MIDC, Above Renault Showroom, Pimpri-Chinchwad, Pune - 411019
Kind Attn: Mr. Dyneshwar Kumbhar
Mob: +91-9168940333 **Email:** procurement@nihva.com

TECHNO-COMMERCIAL OFFER

Sr. No.	Description	Unit	Unit Rate	QTY	Amount
1	5 Ton X 5 Mtr Span X 6 Mtr Height Goliath crane includes; • Main girder • End carriages with geared motor • Cable Track for cross travel cable movement • Electrical panel with VFD in LT motion • All electrical cables Wire Rope Hoist • 5 Ton lifting capacity • limit switch for up down movement • CT limit switch	Nos	827500	1	827500
2	Bus bar for crane supply	Per Mtr	906	1	906
3	Current Collector (4 Nos.)	Nos	5625	1	5625
4	Erection & comissioning	Nos	15000	1	15000
5	Track for crane travel with 50 mm Square Bar (Bay Length 30 Meter Aprrox.)	Nos	310000	1	310000
Total In Words: Eleven Lakh Fifty Nine Thousand Thirty one rupees only		**Basic Total:**	**1159031**		

Remark: Hydra for material movement and erection work will be in client scope

We thank you for your enquiry and are pleased to quote on the following terms & conditions, unless otherwise modified by us in writing. Wetrust our offer meets your requirement and look forward to receiving your valuable Purchase Order

TERMS & CONDITIONS:

Price Basis: Ex-Works Pune	**Ins./Freight/Octroi:** At Actuals to your A/c
Payment Terms: 60% advance and 40% against PI before dispatch	**Delivery:** 4-6 Weeks from Receipt of acceptable PO
Packing & Forwarding: Inclusive	**Validity:** 30 Days
Taxes: GST @18% extra or as applicable at the time of delivery	**Transit Insurance:** By Purchaser

Thanking you and assuring you of our best services and prompt attention at all times.

Thanks & Regards,
Athang Safety & Engineering Solutions, Pune

5 Ton Capacity X 5 Meter Span X 6 Meter Height Single Girder Goliath Crane Kit

Safe Working Load	5 Ton
Operation	From Independent Pendant Push Button control station.
Location	Indoor
Span	5 Meter
Height of Lift	6 Meter
Hoisting Speed	3-7 m/min;
Long Travel Speed	15-18 m/min
Cross Travel Speed	4-15 m/min;
Hoist Motor Rating	5 Hp
Long travel motor Rating	1 Hp Two Nos.(Hindustan make)
Cross Travel Motor Rating	0.5 Hp
Hoist Brake Type	DC Electromagnetic disc brake
Long Travel Brake	DC Electromagnetic disc brake
CT Wheel Diameter	160 mm dia; 4nos
Wire rope	Dia.11mm,6 X 36 Construction, Steel Core
Hoist Number of Falls	4
Power / Control Voltage	415V, 3Phase, 50Hz / 110V, 1Ph, 50Hz