NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rohan Builders (India) Pvt. Ltd.
1 Modibag,Commercial Building,
Ganeshkhind Road, Shivaji Nagar,
Pune - 411016

Date : 04.12.2020
Quote NO : SQT.20.21.2756
Kind Attn : Ajay Mahade
Email Id : inquiry.ho@rohanbuilders.com
Contact No: 9860502997

Project Name & Location: Chennai

Subject : Quotation for Motorised Rolling Shutter, Dock Leveler, Dock Shelter and NIHVA Make High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Insulated Motorized G I Rolling Shutter	3000	3000	11	130,000	1,430,000	15,000	165,000
2	Insulated Motorized G I Rolling Shutter	3000	4000	1	155,000	155,000	15,000	15,000
3	Pre Coated Motorized G I Rolling Shuter	3000	4000	1	110,000	110,000	15,000	15,000
4	Pre Coated Motorized G I Rolling Shuter	5000	6000	1	205,000	205,000	15,000	15,000
5	Automatic Sectional Door Vertical Lift	3000	4000	32	250,000	8,000,000	15,000	480,000
6	Dock Leveller 9 Ton	2200	3000	21	200,000	4,200,000	15,000	315,000
7	Retractable Dock Shelter	3000	4000	21	90,000	1,890,000	15,000	315,000
8	NIHVA Make High Speed Door	3000	3000	1	280,000	280,000	15,000	15,000
				Total		**16,270,000**		**1,335,000**
9	P&F Charges			3%		**488,100**		
	Total Without Taxes					**16,758,100**		**1,335,000**
	GST Extra @ 18%			18%		3,016,458		240,300
	Total With Taxes					**19,774,558**		**1,575,300**
10	Transportation Charges					**Extra at Actual**		
11	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter





Sr .No.	**Specification**	**GI Motorized Rolling Shutter**
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Dock Leveler





Sr. No.	**Description**	**Specifications**
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	0.1
11	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L)3050 mm x (D)485 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

NIHVA ASSA ABLOY Sectional Door





Sr. No	Description	Specifications
1	Model No	OH1042P
2	Opening Direction & Mounting	Vertical
3	Door produced Based on which certification	Doors produced according to ISO 9000 or ISO 14000 certified.
4	Opening/Closing Speed	0,28 m/s
5	Door Material	GI Steel
6	Panel Thickness	44 mm
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Wind Load	EN21424 class 3
11	Thermal Transittance	6 W/m2K
12	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	Emergency Operation	Single phase 230V direct drive on shaft
14	Operating Switch	by Disengagement rope manual
15	Environmental Green Product DeclarationCertification	Up/Down Keypad + stopbutton
16	Drive Unit & Mounting Type	as per ISO 14025 and EN 15804
17	Door Safety	Doors equiped with spring break device; Safety Photo cell, bottom safety edge, rope break mechanism etc.

Retractable Dock Shelter

Sr. No	Description	Specifications
1	Size	(W) 3000 mm x (H) 4000 mm
2	Top Curtain	1000 mm
3	Side Curtain	600 mm
4	Curtain colour	Black
5	Parking Guides	White, Yellow
6	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
7	Top & Side Curtaiins	Double Layer High Quality Polyester
8	Thickness	3.0 mm
9	Weight	Approx 3400 g/m2

NIHVA Make High Speed Door

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	NIHVA Make High Speed Door
1	Use	Internal Door
2	Control Panel	4 Push Button operated
3	Security Features	EN 13241-1 Standard
4	Resistance to wind load	EN12424 upto class 1
5	Curtain	Fabric Transparent PVC section
6	Guide Material	Aluminum
7	Hood Cover	GI
8	Motor Cover	GI
9	Operator & Control	German Make Motor
10	Connecting Voltage	220V , 1Ph , N
11	Open-Stop-Close Button	Standard
12	Protection Category	IP 54 / IP 65
13	Power Consumption	0.75 kw Motor
14	Emergency Off Button	Standard
15	Closing Zone Monitoring	Optical Safety edge
16	External Route Monitoring	Photocell
17	Emergency Opening	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9-10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd