NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

RBCC
Pune, India

Date : 03.02.2020
Quote NO : SQT/20-21/2640
Kind Attn : Mr.SANJAY MULAY
Email Id : rbcc.office1@gmail.com
Contact No: 9881196056

Subject : Quotation for Rolling Shutter and Hign Speed Door.(Project Location - Steel Sevice Center Private Limited ,Bhagapura GIDC, Gujarat)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Rolling Shutter**	5000	6000	5	241,000	1,205,000	20,000	100,000
2	**Motorized Rolling Shutter**	3000	5000	2	155,000	310,000	20,000	40,000
3	**Motorized Rolling Shutter**	4000	5000	1	179,000	179,000	20,000	20,000
4	**Motorized Rolling Shutter (Grill)**	5000	6000	5	250,000	1,250,000	20,000	100,000
5	**Motorized Rolling Shutter (Grill)**	3000	5000	2	148,000	296,000	20,000	40,000
6	**Motorized Rolling Shutter (Grill)**	4000	5000	1	187,000	187,000	20,000	20,000
7	**High Speed Door (RR 392)**	6000	5000	5	1,015,000	5,075,000	20,000	100,000
8	**High Speed Door (RR 392)**	3000	5000	1	842,000	842,000	20,000	20,000
				Total		**9,344,000**		**440,000**
9	P&F Charges			3%		280,320		
	Total Without Taxes					9,624,320		440,000
	GST Extra @ 18%			18%		1,732,378		79,200
	Total With Taxes					**11,356,698**		**519,200**
10	Transportation Charges					In Client Scope		
11	Unloading Charges @ Site					In Client Scope		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

B) Technical Specification

Sr. No	Description	ASSA ABLOY-ALBANY Rapid Rollup Door RR392
1	**Construction:**	High-Speed Roller Door with transparent curtain and blue (similar RAL 5002) reinforcement stripes, optional red (similar RAL 3002). Door with curtain tension.
2	**Drive Unit:**	motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
3	**Control system:**	MCC Frequency converter for opening/closing speed up to 2,2 / 0,9 m/s.Power supply required 3L(N)PE 400/415 V, 50 Hz. Protection IP 55.
4	**Power supply:**	3/(N)/PE/230/400/415 V, 50 Hz.
5	**Safety features:**	Safety contact edge, Safety photocell transmitter / receiver inside side columns.
6	**Hood Cover**	GI Cover
7	**Motor Cover**	GI Cover
8	**Emergency Operation**	By Hand Crank

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd