NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Soch Foods
GB-7, Virwani Industrial Estate,
Near Western Express Highway, Goregaon East,
Mumbai 400063

Date : 06.10.2021
Quote NO : **AS_21.22.0007**
Kind Attn : Mr. Sachin Zanzrukiya
Email Id : orders@sochfoods.com
Contact No: 9321857625

Project Name & Location: Soch Foods, Mumbai

Subject : Quotation for Secondary Packaging Machine

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation considering 03 people for 03 days per conveyor in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Secondary Packaging Machine (without triangle folding station)**	**1**	**9,15,000**	**9,15,000**	**50,000**	**50,000**
2	**Triangle Folding Station**	**1**	**1,25,000**	**1,25,000**		
		Total		**10,40,000**		**50,000**
	P&F Charges	3%		**31,200**		
	Total Without Taxes			**10,71,200**		**50,000**
2	GST Extra @ 18%					**Extra At Actual**
3	Transportation Charges					**Extra At Actual**
4	Insurance Charges					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Secondary Packaging Machine

Sr. No.	Parameters	Specification
1	Material to be conveyed	Sqaure & Triangular Boxes
2	Maximum Product Size	240mm (L) x 200 mm (W) x 30mm (H)
3	Maximum Weight of Box/Bag	250 gm
4	Capacity	20 Boxes Per min
5	Product filling type	Manual
6	Conveyor infeed height	650 mm
7	Contact parts	SS-304 buffed
8	Non-Contact Parts	MS
9	Gear Box	Bonfiglioli
10	Motor Makr	Bonfiglioli/Mitsubishi servo
11	Rest of things	As per layout
12	Output conveyor	Flat belt conveyor

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 8551093333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd