NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1644 R **Date : 18.06.2019**

RMK INFRASTRUCTURE PVT LTD
Talegaon

Kind Attn: Mr. Nisar
Email: coordinator_continental@rmkinfrastructure.com
Mob.No. 7030940677

Project Name And Location :

Subject: Quotation for Scissor Lift

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Price/Each	Net Amount INR
A	**Scissor Lift**				
	1) Capacity :- 2 ton 2) Platform size :-2000 mm (W) x 2000 mm (L) 3) Maximum Height :- 2000 mm 4) Lift Height :-1500 mm 5) SHut Height :- 500 mm 6) Power Pack :- 3 HP, 3 phase 7) Lifting time : 80 sec 8) Lowering time : 60 sec 9) Safety railing : only length side 900 mm ht. 7) Colour : Golden Yellow 8) Main supply cable in client scope.				
1	Supply + Installation	2	No	465,000.00	**930,000**

GST Pune	27AAECN0437H1ZM	**Grand Total**	**930,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places
3. Provide electrical cables near to the installation machinery
4. Hydra/crane at the time of Installation will be in NIHVA Scope.

Limit of Supply

1. Provide place to store the material to be installed
2. Be responsible for the safe custody of all material
3. Provide change & rest room for the workers

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Electrical connection for control panel

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. NIHVA Will provided structure drawing only if required
4. Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	Nil
3	**Freight Notes**	:	Inclusive
4	**Delivery**	:	5 -6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with confirmed order, 20% before dispatch
6	**Taxes**	:	GST Extra @18%
7	**Validity**	:	Validity of Offer is 15 days from the date of quotation.
8	**Warranty**	:	24 months from the date of supply

Please feel free to Contact **Mr. Ravindra Kharat** on **7410169333** for any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd