NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Fresh Link Agro Cold Storage Pvt. Ltd.

Date : 06.03.2020
Quote NO : SQT/19-20/2485
Kind Attn : Mr. Jayant Joshi
Email Id : freshlinkcs7@gmail.com
Contact No: 8530919955

Subject : Quotation for Sectional Door , Sliding Gate and Dock Leveller . (Project - Fresh Link Agro Cold Storage Pvt. Ltd.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Sectional Door**	2500	3000	1	250,000	250,000	20,000	20,000
2	**Manual Sectional Door**	2500	3000	1	190,000	190,000	20,000	20,000
3	**Motorized Sliding Gate**	5750	1300	1	395,000	395,000	20,000	20,000
4	**Wicket Gate**	1000	1800	1	133,000	133,000	20,000	20,000
5	**Dock Leveller - 9 Ton**	2000	2500	2	210,000	420,000	20,000	40,000
6	**Dock Leveller - 15 Ton**	2000	2500	2	225,000	450,000	20,000	40,000
7	**Single Leaf Hinged Door (Panel Thickness - 80 mm)**	1200	2100	18	35,000	630,000	20,000	360,000
8	**Double Leaf Hinged Door(Panel Thickness - 80 mm)**	1500	2100	3	62,000	186,000	20,000	60,000
9	**Double Leaf Hinged Door(Panel Thickness - 80 mm)**	1800	2100	1	67,000	67,000	20,000	20,000
10	**Double Leaf Hinged Door(Panel Thickness - 80 mm)**	2000	2100	6	76,000	456,000	20,000	120,000
11	**Single Leaf Hinged Door (Panel Thickness - 120 mm)**	1200	2100	2	45,000	90,000	20,000	40,000
12	**Double Leaf Hinged Door (Panel Thickness - 120 mm)**	1500	2100	2	70,000	140,000	20,000	40,000
				Total		**3,407,000**		**160,000**
13	P&F Charges			3%		102,210		
	Total Without Taxes					3,509,210		160,000
	GST Extra @ 18%			18%		631,657.80		28,800
	Total With Taxes					**4,140,868**		**188,800**
14	Transportation Charges					In Client Scope		
15	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification





Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Opening/Closing Speed**	0.25 m/s	
2	**Door Material**	GI Steel with PUF inside	
3	**Panel Thickness**	42mm	
4	**Panel colour**	RAL 9002 Powder coated	
5	**External surface of the panel**	diamond grid design with a glossy finish at the section joints.	
6	**inside surface of the panel**	Monolithic surface on the inside of the door	
7	**Broken cold bridge**	Section joints with broken cold bridges	
8	**Door sealent**	All door sealants made of EPDM rubber.	
9	**All Panel height**	All panels should be 545mm high	
10	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
11	**Steel component Material**	All steel components to be electro galvanized	
12	**Hinge Material**	Glass fibre reinforced Polyamide	
13	**Panel Thickness**	42 mm	
14	**Spring Material surface finish**	Powder coated	
15	**Water Penetration**	EN 12425	class 3
16	**Air Permealibity**	EN12426	class 2
17	**Wind Load**	EN21424	class 3
18	**Thermal Transittance**	EN 12428 1.10W /m2K	
19	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
20	**Door saftey device 1**	Doors equiped with spring break device	
21	**Door saftey device 2**	Door equiped with pneumatic safety edge	
22	**Door saftey 3**	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	
23	**Incase of Power failuer**	One can operate the Door manually	
24	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
25	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft	
26	**Emergency Operation**	by Disengagement rope manual	
27	**Operating Switch**	Up/Down Keypad + stopbutton	
28	**Environmental Green Product Declaration Certification**	as per ISO 14025 and EN 15804	





NIHVA make – Motorized Sliding Gate	
Door type	**Motorized Sliding Gate**
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Technical Specification

Sr .No.	Specification
1	**Single leaf/Double Leaf Hinged Door 80 mm thickness for Positive temp.**
2	**Density** **42kg/m3) with 0.6 mm PPGI RAL 9003 (Both Side)**
3	**EPDM Gasket, Cladding , with emergency** **unlocking arrangement from inside**

Sr .No.	Specification
1	**Single leaf/ Double Leaf Hinged Door 120 mm thickness for Negative temp.**
2	**Density** **42kg/m3) with 0.6 mm PPGI RAL 9003 (Both Side)**
3	**EPDM Gasket, Cladding , with emergency** **unlocking arrangement from inside.**
4	**Heating Arrangement: - Supplied with heating cables in threshold. The threshold which is manufactured of anodized aluminium is to be placed into the floor. Alternatively, the door can be upplied without a threshold, if supplied with extra heating at bottom of the door blade.**


NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification





Description	Specifications
Capacity	9 / 15 Ton
Dock operation mode	AC power pack hydraulically operated
Lip operation mode	Hydraulic
Operation control	Through panel
Loading platform height from road	1250mm
Travel above & below dock level	(+) 300 / (-) 250 mm
Platform Size (W x L)	2000 mm x 2500 mm
Lip size (W x L)	2000 x 400 mm
Shut Height	480 mm
Overall length	2000mm x 2500mm + Lip Length (400mm)
Maximum slope can be achieved	10%
Clear Pit dimensions (W x L x D)	(W) 2050mm x (L) 2050 mm x (D)485 mm
Hydraulic power pack	Standard
Driver type	Direct by electric Motor
Motor Ratings	1 H.P
Pump design flow	2.5 LPM
Pump pressure	120 bar Operating 200 bar Max.
Safety valve set pressure	120 Kg/cm²
Pump Type	Gear
Volume of oil receiver	7 Lit
No Of Deck cylinder	2 No
Lip Cylinder	1 No
Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 855192333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd