NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tenneco Clean Air india Pvt. Ltd.
Chakan
Pune
Maharashtra, India

Date : 17.12.2020
Quote NO : SQT/20-21/0047R1
Kind Attn : Mr. Shrikant Malave
Email Id : SMalave@Tenneco.com
Contact No: 9922946534

Subject : Quotation for High Speed Door RP300 - High Sea Sale

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR (High Sea Sale Pricing)		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany make Machine Protection Door RP300**	1800	2000	4	4,94,000	19,76,000	-	-
2	**Albany make Machine Protection Door RP300**	1500	1000	1	4,78,000	4,78,000	-	-
3	**Air Frieght Chagres**			1 Set	3,75,000	3,75,000		
				Total		**28,29,000**		
4	P&F Charges			0%		-		
	Total Without Taxes					28,29,000		-
5	Transportation Charges					Extra at actual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Details
		Albany make Machine Protection Door RP300
1	Door version:	**Vertical Rapid Roller Door for machine protection.**
2	Side Frames:	**Aluminum anodized two parts, to have easy access to switches and service.**
3	Door blade:	**Rolltex Plus Curtain with RAL Blue 5002**
4	Bottom beam	**Aluminium anodized.**
5	Drive unit:	**Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)**
6	Opening / closing speed:	**Approx. max. 2,4 / 1,7 m/s**
7	Control system:	**MCC Vector Control**
8	Power suppy:	**3/(N)/PE 230/380/400/415 V, 50 Hz**
9	MCC Display	**Included, delivered separately**
10	Safety features:	**Safety edge with cable chain integrated in side frames, pre running photocell.**
11	Safety limit switch:	**1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.**
12	Window Type	**700 x 500 mm Anti UV Type**
13	Motor Cover	**Included**
14	Hood Cover	**Included**
15	Window Qty	**1 No**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Above prices are excluding all other structural members required for installation of the door and Taxes.
2. Complete structural design, build are in client scope.
3. **Above prices are CIF prices by Sea which are without any Custom duty, Custom Clearance, Local Transport**
4. There will be High Sea Sales agreement between NIHVA and Tenneco Automotive. and this is to signed by both parties before arrival of equipment at Seaport.
5. Since this is Sea consignment both the parties will have to take at most care during this transaction as the agreement is required to discharge in between the period of dispatch and receipt at sea port
6. For any reason if consignment gets hold at custom NIHVA will not be responsible for any delayed charged or penalty.

Client Scope of Work:

1. Custom Duty + Custom Clearance + Local Transport, till site in clients Scope. NIHVA will handover BL to client for further all process & action till material reaches at site & unloads at required place.
2. For High Sea sale responsibility of NIHVA ceases on transfer of BL to client.
3. Client should issue required forms to NIHVA for all Tax Exemptions.

Note: **Please find below List which are in Client Scope**

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) **Terms & Conditions**

Price	: CIF Nava Seva Port
Delivery	1) By Sea Freight : 12 - 13 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval. 2) By Air Freight : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd