NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0099 **Date : 27-02-2018**

Siemens Limited
E-76, Waluj MIDC Area
Aurangabad
Maharashtra,India

Kind Attn : Mr. Abhay Kharkar
Email : Abhay.kharkar@siemens.com
Contact No : 9823151841

Subject : Quotation for Vibratory Bowl & Linear Feeder

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**Vibratory Bowl Feeder Make : Nihva**	1	No	98,000	98,000
	• Part Name/ Material : Silver Tungs				
	• Model : 200 mm Dia				
	• Bowl Type : 200 mm Step Model				
	• Bowl Material : SS, 2.5mm thickness, Non Magnetic				
	• Vibrator Bowl Direction : Clockwise				
	• Vibrator Drive : Base Plate - CI Casting & Top Plate - Al Casting				
	• Inclination Degree Of Outlet Track : 30 degree				
	• Outlet Track Material : SS				
	• Magnetic Coil : 170 VA, 50 HZ				
	• Voltage Controller : Supply 180-260 VAC/ 50 Hz, Current 3/6/10/15 Ampere Track Control - On/Off Delay Optional, Overload Protection Setting Via Potentiometer 0 to 10 V or 4 to 20 MA External Enable/Disable Connection, Built in Soft Start setting				
2	**Linear Feeder Make : Nihva**	1	No	77,000	77,000
	• Guide Material: SS, Machined Guide				
	• Vibrator Drive : Base Plate - MS & Top Plate - Al Casting				
	• Guide Length : 500 mm				
	• Feed Rate Per Sec : As per your requirement				
	• No. of outlet Track : Single Track				
	• Magnetic Coil : 170 VA, 50 HZ				
	• Voltage Controller : Setting Via Potentiometer 0 to 10 V or 4 to 20 MA Track Control - On/Off Delay Optional, Overload Protection External Enable/Disable Connection Automatic Voltage Regulation Built in Soft Start & Course Fine Setting				
3	**Main Stand with Anti Vibration Pads**	1	No	20,000	20,000
4	**High / Low Level Sensor Stand**	1	No	5,000	5,000
5	**Installation & Training Charges For Above**	1	Set	20,000	20,000

GST PUNE:	**27AAECN0437H1ZM**	**Total Amount**	**2,20,000**
		Amount in Words	**Rupees Two Lacs Twenty Thousand Only**

The supply included only those mentioned in the quote & does not include

1 Any Civilwork will be in your scope. Crane for unloading and installation part will be provided by you.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: Extra as applicable at the time of delivery.
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd