NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Patil Automation
Chakan

Date : 16.10.2020
Quote NO : SQT.20.21.2770
Kind Attn : Mr.Sandeep Chaudhari
Email Id : sschaudhari@patilautomation.com
Contact No: 7030913060

Subject : Quotation for Manipulator

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Manipulator**			2	1,232,000	2,464,000	20,000	40,000
	Total			**2**		**2,464,000**		**40,000**
2	P&F Charges			3%		73,920		
	Total Without Taxes					**2,537,920**		**40,000**
	GST Extra @ 18%			18%		456,826		7,200
	Total With Taxes					**2,994,746**		**47,200**
3	Transportation Charges				Extra at Actual			
4	Unloading Charges @ Site				In Client Scope			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Manipulator

Sr .No.	Specification	Manipulator
1	**Load Capacity**	100kg (Gripper + Component) - at 6 bars
2	**Arm Size**	First Arm -1.3mtr and 2nd arm -1.2mtr
3	**Gripper Weight**	50 Kg
4	**Working Radius**	Approximately 2.1meters (layout based) A detailed layout will be drafted for the fixture station. Based on kinematic design, the working reach and radius will be defined and decided.
3	**Lifting Stroke (Vertical)**	1450 mm
4	**Brakes at rotary joint**	Brakes actuate in case of loss of air.
4	**Balance control**	Manually adjustable balance control. Special balancing control knob, which will be located close to operator hand, for fine setting of balance during handling. Change over from load to no-load condition and vice versa will be fully automatic.
5	**Content of the system**	Articulated arm type manipulator with up and down. Pneumatic gripper. Operator pendant with push buttons. Parking brakes for all rotary joints. (3 nos.) Spiral pneu. Tubing with brackets for mounting. FR unit.
6	**Safety features**	Standard safety features

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Work Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd