NIHVA
NIHVA TECHNOLOGIES PVT. LTD.







LM Wind Power Blades

Dabaspet, Bangalore India



Quotation

ASSA ABLOY

ASSA ABLOY Entrance Systems

The global leader in
door opening solutions

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No. SQT/18-19/0499R6 **Date: 27/05/2019**

LM WIND POWER BLADES
Plot No-85, KIADB Industrial Area-
Phase II, Dabaspet, Nelamangala Taluk,
Bangalore (Rural Dist) - 562111

Kind Attn: Mr. Santosh Naik
Email: rnt@lmwindpower.com
Contact No: 09886811532

Project Name and Location: LM Wind Power Blades Project at Dabaspet, Bangalore.

Subject: Supply and installation of Electrically operated Vertical Lifting Fabric Door (Megadoor) for Size 6000 mm X 7000 mm.

Dear Sir,

Thank you for giving us an opportunity to participate with our offer on the above project. We enclose herewith our proposal which includes:

A. Requirement
B. Proposal
C. Terms and Conditions
D. Pricing

By choosing ASSA ABLOY Entrance Systems as the supplier of your door automation products, you will receive the following advantages:

- You are working with a Global Provider with financial strength and over 50 years' experience of the global market place in Entrance Solutions.
- World leading products ensure excellent reliability and life-cycle costs to give you peace of mind.
- Project support for both specification development and design suitability
- A comprehensive product helping to provide value engineered solutions

Major Benefits using Megadoor

- No floor track (and therefore no concrete grade beam) needed; a substantial saving in civil cost.
- Good opening speed and closing time due to vertical lifting, resulting in a substantial reduction in loss of energy.
- Minimal side-room required (no "door pockets"); a substantial saving in space and cost of land, this is especially relevant, when a series of hangars are built adjacent to each other.
- The doors have very tight sealing, to protect against water, sand and dust ingress, which is essential for a maintenance hangar.

We wish you success with your project and hope that we may be part of your current & future projects as a solution provider. We will follow up this quotation with a call to you within the next few days.

If you have any questions after reading this proposal, or if you need more information, please do not hesitate to contact us.

Kind Regards,
Ms. Varsha
NIHVA Technologies Pvt. Ltd
Mob: +91 8551091333 Email: support@nihva.com

Description: -

- The door leaf consists of two sheets of PVC-coated polyester fabric that withstand a temperature of –35 to +70 degrees C. Intermediate horizontal aluminum sections are fitted between the inner and outer fabric.

- The door leaf is opened by belt/wire ropes attached to the bottom section; these are wound up onto a hoist unit. The TUV Approved safety arrester will prevent the door from falling in the unlikely event of wire failure. A wind lock system is also included to prevent the door from lifting under high wind load conditions.

- The door leaf is guided with aluminium side-guides mounted in the door frame.

- The door is available in the following standard colors: Red (RAL 3001), Blue (RAL 5005), Grey (RAL 7004), White (RAL 9016), Tan (RAL 1001), Green (RAL 6009) or Translucent White. Other colours are available at an extra cost.

- The door is operated via a touch screen control panel which includes visual indication of the door status and fault diagnosis indication plus Service history data. The enclosure of the control cabinet meets the specifications of protection class IP65, Push buttons IP65 and Gear motor IP55.

- Electrical cables as per EN regulations. Cable tray and/or conduit is excluded.

Installation equipment's like Telehandler, Scissor Lift, Heavy Duty Crane, Boom lift to be provided by LM Wind Power Blades.

Commercial Offer: -

Supply of VL3110 Vertical Lifting Fabric Door

Sr No.	Description	Qty (NO'S)	High Sea Sales Supply (INR)
1	**Clear Size in mm (W) X (H)** (W) 6000 mm X (H) 7000 mm	1	9,07,000
2	Push button station up-stop-down	1	23,500
3	2 sets Photocell with reflector	1	29,750
4	Remote control - radio receiver & Transmitter	1	34,000
5	Flashing Light	1	8500
6	Air Freight Charges		120000
7	Scissor Lift for Two Days	1	32,000
8	Structure for Door	1	17,500
9	Local Transport		33,500
10	Installation & Commissioning Charges	1	20000
11	AMC Charges	1	30000
		Total	Rs 12,55,750

Note:

1. **If you have benefits of Duty Custom Duty + Custom Clearance charges can be waved off.**
2. **Doors are designed to withstand a wind load of 0.8Kpa (approx. 130Km/hr. speed), in addition to this we have safety factor of 1.21 for ultimate limit state.**

Note for High Sea Sales Agreement:

1. There will be High Sea Sales agreement between NIHVA and LM Wind Power Blades Pvt Ltd and this is to signed by both parties before arrival of equipment at Airport

2. For any reason if consignment gets hold at custom NIHVA will not be responsible for any delayed charged or penalty.

Client Scope of Work:

1. For High Sea sale responsibility of NIHVA ceases on transfer of AWB to client.

2. Client should issue required forms to NIHVA for all Tax Exemptions.

General Pre-Requisites Required at Site

Prerequisites:

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery.

Limit of Supply

1. Provide place to store the material to be installed.
2. Provide place to safely store all the tools of installation.
3. Provide change & rest room for the workers.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service Technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope.

Terms & Conditions:

Payment	Immediate after 30 Days from the date of Invoice.
P & F Charges	NIL
Transport	Mentioned above
Tax	GST @ 18% Extra
Validity	15 days from the date of offer
Delivery	➢ Mfg. time = 4 weeks from the date of approval ➢ Air fright = 1 week (considering all custom duty's/clearance formalities and local traveling from Mumbai to Bangalore) Hence total = 5 weeks ➢ Installation time: Min 2-3 days after receipt of material at site and site availability
Insurance	Extra
Warranty	12 months from date of Supply
Client scope	➢ Once our project gets completed; for any additional work to & fro, lodging & boarding of our service technicians is in client scope. ➢ Any masonry / structural work required to support are in client scope
Compensation clause	Please note that in the event the buyer cancels an order, after order is confirmed to us, it is binding to the buyer to pay NIHVA - ASSAABLOY a compensation of 25% of order value.
Drawings	We will issue a full set of shop drawings for approval within 2 weeks of receiving the confirmed order and finalized design details
Others	Need to provide by client - clear opening mounting structures, any Civil work, electrical points and cables till doors, Material and equipment storage secured space, fabrication and assembly space.

Scope of supply

The scope includes: Design, production, delivery and Supervision or installation of door as described in the attached technical specification.

For technical specifications, sketches, pictures and similar, please see Appendices.

A suitable structure should be available designed in accordance with final approval drawings issued by NIHVA_ASSA ABLOY. Tolerances/deflections of the support structure to be in accordance with the drawings.

General conditions of Hangar Door

1. Continuous uninterrupted access to any single door section or as agreed separately.

2. A clear floor area of 4 meters each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.

3. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 meter of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.

4. Provision of 230 Volt power supply (by others) for hand tools.

5. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.

6. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.

7. Any storage costs for materials due to delays outside of Mega door's control will be charged to the main contractor.

8. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.

9. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Inclusions

1. Our proposal includes **sea freight from Sweden to Dabaspet, Bangalore site and installation of the door leaf, guide rails, weather seals, motors, control panel and electrical wiring.** (refer exclusion).

2. A pre-installation inspection will be carried out, by our Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities are ready for installers.

3. Note that the control panels, motors & electrical wiring are in full compliance with Swedish regulations and specs, any variations due to specific requirements for India must be notified to us at the time of ordering & may be subject to an increase in the price. Any variations notified to us, after material procurement, will be charged accordingly and may lead to production delays.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA - ASSAABLOY.

1. The structural support steel for the door head, jambs, motor plates and motors shall be furnished by others. Structural steel supports shall be installed in accordance with tolerances shown on Megadoor shop drawings. The installation will not commence until these items are fully installed and tested (by steelwork contractor). The installation must be approved by the Megadoor Project Manager.

2. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

3. Power supply and isolators adjacent to the control panels (to be done by electrical contractor).

4. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units be provided. (to be done by electrical contractor). These are to be installed prior to the commencement of door installation.

5. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.

6. A safe storage / pre-assembly area for the door materials (by main contractor).

7. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).

Please feel free to Contact Mr. Mallikarjun Patil on 08551096333 For any further Clarification / Information in this concern.

Kind Regards,
Ms. Varsha
NIHVA Technologies Pvt. Ltd
Mob: +91 8551091333
Email: support@nihva.com

ASSA ABLOY Entrance Systems

One partner for all your automatic entrances

ASSA ABLOY Entrance Systems comprise world-leading products, maintenance programs and modernization services, ensuring total solutions for efficient flow of people, goods and vehicles. With comprehensive entrance solutions for the front, back and interior of your building, we put every automatic door equipment or service you need under one roof.

The perfect match for your building
ASSA ABLOY Entrance Systems' extensive product range, expert application knowledge and maintenance programs provide optimal entrance solutions for all needs and any demands in manufacturing, distribution & logistics, retail, healthcare, transportation, hospitality, private services, public services, mining and air & sea, and more.

Sustainable Solutions
We design, manufacture and service automatic entrance solutions that help you reach your sustainability goals for energy savings and minimal environmental impact.

Leading product brands backed by dedicated specialists
With our three specialized business areas; Pedestrian Door Solutions, Industrial Door & Docking Solutions and High-Performance Door Solutions, we offer market-leading product brands and a global service organization. With more than a century of aggregated engineering experience and application expertise ASSA ABLOY Entrance Systems is your ideal business partner to provide, maintain and modernize all of your automatic entrances.



Pedestrian Door Solutions

- swing doors
- sliding doors
- revolving doors



Industrial Door and Docking Solutions

- industrial doors
- complete docking systems
- hangar doors



High-Performance Door Solutions

- high speed roll doors
- doors for special applications such as clean rooms, machine protection and food processing