**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Kumar World**
**Pune**

**Date :** 15.12.2020
**Quote NO :** SQT.20.21.2885R
**Kind Attn :** Rohit Sardesai
**Email Id :** Rohit.Sardesai@Kumarworld.com
**Contact No:** 7304940259

**Subject : Quotation for Double Leaf Telescopic Sliding Gate, Single Leaf Sliding Gate and Wicket Gate**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Double Leaf Telescopic Sliding Gate | 7000 | 1900 | 1 | 486,000 | 486,000 | 20,000 | 20,000 |
| 2 | Single Leaf Sliding Gate | 5000 | 1900 | 1 | 321,000 | 321,000 | 20,000 | 20,000 |
| 3 | Wicket Gate | 1200 | 1900 | 1 | 40,000 | 40,000 | 10,000 | 10,000 |
| | | | | **Total** | | **847,000** | | **50,000** |
| 4 | P&F Charges | | | 3% | | 25,410 | | |
| | **Total Without Taxes** | | | | | 872,410 | | 50,000 |
| | GST Extra @ 18% | | | 18% | | 157,033.80 | | 9,000 |
| | **Total With Taxes** | | | | | **1,029,444** | | **59,000** |
| 5 | Transportation Charges | | | | | In Client Scope | | |
| 6 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Telescopic Sliding Gate**

| Sr .No. | Specification | Telescopic Sliding Gate |
|---|---|---|
| 1 | Door type | Motorised Double Leaf Telescopic Sliding Gate |
| 2 | Master Leaf Size | 5000 X 1875 mm |
| 3 | 1 ST Leaf Size | 4400 X 1875 mm |
| 4 | Opening Direction | Horizontal - from left to right or reverse |
| 5 | Mounting Location area | Inside area |
| 6 | Design Pattern | Standard Tubular Design Pattern |
| 7 | Outer Frame Tube Sizes | 72 x 72 x 3.2mm MS SQ. TUBE |
| 8 | Internal Vertical Tube Sizes | 25x25x2.6mm MS SQ. TUBE |
| 9 | For Post | 72 x 72 x 3.2mm MS SQ. TUBE |
| 10 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 11 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings |
| 12 | Guide Rollers supporter during Gate movement | Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate |
| 13 | Painting | Two Coats of Primer and Two Coats of Synthetic Enamel Paint |
| 14 | Control Panel | 2 Nos Operating Station.( Motor Panel and Security Room) |
| 15 | Operation | By Telescopic Mechanism |
| 16 | Accessories | 1. Limit Switch for Cut out when Gate is fully Closed |
| | | 2. Flashing Light |
| | | 3. Hooter |
| | | 4. Photocell |

**Motorized Single Leaf Sliding Gate**

| Sr .No. | Specification | Motorized Single Leaf Sliding Gate |
|---|---|---|
| 1 | Door type | Motorized Sliding Gate |
| 2 | Opening Direction | Horizontal - from left to right or reverse |
| 3 | Mounting Location area | Inside area |
| 4 | Design Pattern | Standard Tubular Design Pattern |
| 5 | Outer Tube | 72 x 72 x 3.2mm MS SQ. TUBE |
| 6 | For Post | 72 x 72 x 3.2mm MS SQ. TUBE |
| 7 | Innear Tube | 25x25x2.6mm MS SQ. TUBE |
| 8 | Gap Between Tubes | 125mm |
| 9 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 10 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| 11 | Guide Rollers supporter during Gate movement | Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate |
| 12 | Painting | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| 13 | El motor make | BFT – Italy (100% imported) |
| 14 | Emergency Operation | Manual after turn the switch |
| 15 | Operating Switch | Push Button from inside |
| 16 | Safety | Photocells, Flashing Light |

**Wicket Gate**

| Sr .No. | Specification | Telescopic Sliding Gate |
|---|---|---|
| 1 | Door type | Manual Single Leaf Wicket Gate |
| 2 | Mounting Location area | Inside area |
| 3 | Design Pattern | Standard Tubular Design Pattern |
| 4 | Outer Frame Tube Sizes | 72 x 72 x 3.2mm MS SQ. TUBE |
| 5 | Internal Vertical Tube Sizes | 40 x 40 x 2 mm |
| 6 | Gap Between Tubes | 100 mm C/C |
| 7 | Painting | 2 Coats of EPOXY polyamide based enamel finish of approved Colour |
| 8 | Operation | Manually Opening |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd