**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Tenneco Clean Air india Pvt. Ltd.**
Chakan, Pune

**Project, Location :**

**Date :** 13.02.2021
**Quote NO :** SQT.20.21.3014R
**Kind Attn :** Mr. Shrikant Malave
**Email Id :** SMalave@Tenneco.com
**Contact No:** 9922946534

**Subject : Quotation for High Speed Door RP300 - NIHVA Make**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **NIHVA make Machine Protection Door RP300 - BY SEA FREIGHT** | 1800 | 2000 | 2 | 350,000 | 700,000 | | - |
| | **Total** | | | **2** | | **700,000** | | **-** |
| 2 | P&F Charges | | | 3% | | 21,000 | | |
| | **Total Without Taxes** | | | | | 721,000 | | - |
| | GST Extra @ 18% | | | 18% | | 129,780.00 | | - |
| | **Total With Taxes** | | | | | **850,780** | | **-** |
| 3 | Transportation Charges | | | | | Extra at atcual | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**NIHVA Make Machine Protection Door RP300**

| Sr. No | Specification |
|---|---|
| 1 | Aluminium side columns anodized E6/EV1 Rapida model<br>( 3.5 mm thickness Consists of two parts ) |
| 2 | Curtain from 2 mm orange or blue rolltex material with 1with special windnopp roller on side mounted. |
| 3 | Aluminium blank rigid drum ( 4 mm thickness ) |
| 4 | Aluminium anodized E6/EV1 bottomprofile with rubber profil finishing |
| 5 | 1.5 hp gearmotor with digital encoder |
| 6 | mr220 inverter driver |
| 7 | Lightcurtain ( CEDES or WITT brand depand on stok ) |
| 8 | 1 pc. Mushroom button |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd