**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

RATILAL BHAGWANDAS CONSTRUCTION COMPANY
Pune

**Date : 04.09.2019**
Quote NO : SQT.19.20.2017
**Kind Attn : Mr. Sanjay Mulay**
Email Id : sanjay.mulay@ratilal.in
Contact No: **9881196056**

**Project Name & Location:** Dapodi, Pune

**Subject : Quotation for Double wall GI Rolling Shutter**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Double Wall GI Rolling Shutter | 4000 | 4000 | 2 | 298,000 | 596,000 | 20,000 | 40,000 |
| 2 | Double Wall GI Rolling Shutter | 4000 | 3000 | 5 | 261,000 | 1,305,000 | 20,000 | 100,000 |
| 3 | Single Leaf Motorised Gate | 6000 | 1200 | 1 | 370,000 | 370,000 | 20,000 | 20,000 |
| 4 | Wicket Gate | 1500 | 1200 | 1 | 30,000 | 30,000 | 10,000 | 10,000 |
| | | | | **Total** | | **2,301,000** | | **170,000** |
| 5 | P&F Charges | | | 3% | | **69,030** | | |
| | **Total Without Taxes** | | | | | **2,370,030** | | **170,000** |
| | GST Extra @ 18% | | | 18% | | 426,605 | | 30,600 |
| | **Total With Taxes** | | | | | **2,796,635** | | **200,600** |
| 6 | Transportation Charges | | | | | **In Client Scope** | | |
| 7 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| **1. & 2. Double Wall Rolling Shutter** |
|---|
| • GI Slat : 1.0 mm Thick |
| • Profile : Curved Type Profile with heavy duty Shaft |
| • Guide : 2.5 mm Thick MS Guide |
| • Hood Cover & Motor Cover : 0.9 mm Thick GI material |
| • Direct Drive |
| • With Painting |

**3. Sliding Gate**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Door type | Motorised Single leaf Sliding Gate |
| 2 | Clear Opening gate dimension | (W) 6000 mm X (H) 1200 mm |
| 3 | Mounting Location area | Inside area |
| 4 | Design Pattern | Standard Tubular Design Pattern |
| 5 | Outer Frame Tube Sizes | 72 x 72 x 3.2 mm |
| 6 | Internal Vertical Tube Sizes | 38 x 38 x 2.6 mm |
| 7 | Gap Between Tubes | 125 mm C/C |
| 8 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 9 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| 10 | Full Height Column sizes | 100 x 100 x 3.2 mm |
| 11 | Guide Rollers supporter during Gate movement | Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate |
| 12 | Painting | Powder Coating |
| 13 | Installation Checks | need to be check = space requirements + substructure + Mounting access |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd