NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Emerson Export Engineering Centre
Shivajinagar, Pune-411005

Date : 13.07.2021
Quote NO : **MHE_21.22.0021R**
Kind Attn : Mr. Dibakar Mohanto
Email Id : Dibakar.Mohanto@Emerson.com
Contact No: 9922236769/8788355120

Project Name & Location: IOCL-Chennai Lube Project

Subject : Quotation for Screw conveyor & Roller conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr. No.	Description	Qty	Supply Charges in INR		Installation Charges for in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Horizontal Screw Conveyor 3 mtr**	**1**	**1,66,700**	**1,66,700**	**Based On Location**	
2	**Idler/Gravity Roller Conveyor 2.5 mtr**	**1**	**68,250**	**68,250**		
3	**Idler Roller Conveyor 1.5 mtr with ss-304 roller**	**1**	**50,000**	**50,000**		
4	**Driver Roller Conveyor with weighing scale**	**1**	**3,20,000**	**3,20,000**		
5	**Counting Sensor (P&F-Make)**	**1**	**9,200**	**9,200**		
		Total		**6,14,150**		
	P&F Charges	3%		**18,425**		
	Total Without Taxes			**6,32,575**		
	GST Extra @ 18%	18%		**1,13,863**		
	Total With Taxes			**7,46,438**		
6	Transportation Charges					**Extra At Actual**
7	Insurance					**Extra At Actual**
8	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification for Truck Loading/Unloading Conveyor

Horizontal Screw Conveyor

Sr. No.	Parameters	Specification
1	Product	Sulphur Powder
2	Product density	890 kg/m3
3	Output capacity	1005 kg/Hr
4	Contact parts	SS-304
5	Non- contact parts	SS-304
6	Gear motor	Bonfiglioli
7	Bearing	SKF/NTN
8	Seals	Oil seals
9	Inlet & outlet flange	As per customer hopper flange

Drive Roller Conveyor with Weighing Scale

Sr. No.	Parameters	Specification
1	Product	Polymer bags
2	Product size	700x 400x 200(LxWxH)
3	Product weight	25 kg
4	Product capacity	Please specify
5	Conveyor capacity	Up to 150 kg
6	Speed of conveyor	10 mtr/min
7	Conveyor infeed height	600 mm
8	Conveyor outfeed height	600 mm
9	Roller	SS-304
10	Non -contact parts	MS powder coated
11	Foot/Caster wheel	Spectra plast/ equivalent
12	Finish	Powder coated
13	Conveyor height adjustment	Through foot 50 +/- mm
14	Weighing accuracy	Least count will be 10 g and accuracy of +/- 20 g
15	System output	4 -20mA
16	Display	Weighing display

Idler/Gravity Roller Conveyor 2.5 mtr

Sr. No.	Parameters	Specification
1	Product	Polymer bags
2	Product size	700x 400x 200(LxWxH)
3	Product weight	25 kg
4	Product capacity	Please specify
5	Conveyor capacity	Up to 150 kg
6	Speed of conveyor	Idler through gravity
7	Conveyor infeed height	600 mm
8	Conveyor outfeed height	500 mm
9	Roller	SS-304
10	Non -contact parts	MS powder coated
11	Foot/Caster wheel	Spectra plast/ equivalent
12	Roller	Chiorino/Forbo/NTB
13	Finish	Powder coated
14	Conveyor height adjustment	Through foot 50 +/- mm

C) General Conditions

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd