NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

TRANS ENGINEERS INDIA PVT. LTD
Vascon Eco Tower, Unit No. 101 & 102
Plot No.3/13/1, Baner-Pashan Link Road,
Baner, Pune- 411 045

Date : 21.2.2021
Quote NO : SQT.20.21.2960
Kind Attn : Jay Gopal Chatterjee
Email Id : jchatterjee@transengineers.com
Contact No: 9975748677

Project, Location : Pune

Subject : Quotation for Flip Flap Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option I	Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Flip Flap Door_0.5mm SS_304 Finish**	2200	2200	3	135,000	405,000	**Inclusive**	
2	**Flip Flap Door_0.5mm SS_304 Finish**	2200	2000	1	130,000	130,000	**Inclusive**	
	Option II							
3	**Flip Flap Door_0.5mm PC_GI Finish Blue Color**	2200	2200	3	125,000	375,000	**Inclusive**	
4	**Flip Flap Door_0.5mm PC_GI Finish Blue Color**	2200	2000	1	120,000	120,000	**Inclusive**	
	Total			**8**		**1,030,000**		**-**
5	P&F Charges			3%		30,900		
	Total Without Taxes					1,060,900		-
	GST Extra @ 18%			18%		190,962.00		-
	Total With Taxes					**1,251,862**		**-**
6	Transportation Charges					Extra at atcual		
7	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

FLIP FLOP DOOR

Sr. No	Description	Specification
1	Leaf	40 mm thickness individually injected in Polyisocyanurate (PIR Insulation) (40-45 kg/m3), leaf with co-extruded EPDM gaskets. Included methacrylate Porthole 400H*280L and extra polyethylene Protection in the base 300 mm heigh.
2	Frame	L-shaped extruded pre coated aluminium with counter frame adapted to all wall panel thicknesses.
3	Hinges	Specially designed stainless steel hinges for intensive use. optional polyamide. optional PCGI leaf finished.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 3 - 4 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd