Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1542 R1 **Date: 20/05/2019**

Newgentech Solutions

AdmIn Office : 402, Priyadarshani , Nr.Shiv Sena office
Thane, Mumbai - 400601
Maharashtra -India

Kind Attention: Mr. Rehman M

Phone:- 9619771158
Email ID: sales@newgentechsolutions.in

Project Name And Location :

Subject : Quote for - Dock Leveller and Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Unit	Total
1.	Dock leveller Platform Size : (W) 2000 mm x (H) 2500 mm Capacity : 15 Ton Dock Operation Mode : AC Powerpack Hydraulically Operated Lip Size : (W) x (L) : 2000 mm x 400 mm Dock Leveller (Shut) Height : 480 mm Working Length : 2900 mm Deck Plate : (M S Chequered) : 8 mm Thick Lip Plate : 16 mm Thick No. of Deck Cylinder : 2 Lip Cylinder : 1	₹ 200,000.00	1	Nos	₹ 200,000.00
2.	Motorised Rolling Shutter Size : (W) 2400 mm x (H) 3000 mm M S Slat : 1 mm Thick Curved Type Profile with Heavy Duty Shaft, Guide, Hood cover, Motor - Indirect Drive with Painting Interlocking considered	₹ 73,000.00	1	Nos	₹ 73,000.00

Sub Total	₹ 273,000.00
Grand Total	**₹ 273,000.00**

GST Pune	27AAECN0437H1ZM

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1542 R1 **Date: 20/05/2019**

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :**Extra As applicable

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** for any further Clarification /Information in this Concern.

With Best Regards

Swapnil Kulat
+91-7219207333
For Nihva Technologies Pvt Ltd