ELEPHANT MATERIAL HANDLING EQUIPMENTS

Ref No : EMHE/2021-2022/00162 **Date : 02/02/2022**

NIHVA TECHNOLOGY

PUNE.

Kind Attn : Mr Dnaneshwar Kumbhar sir,

Sub : Your requirement of 5MT x 5.0M SPAN SINGLE GIRDER Goliath Floor operated type EOT Crane & Gantry crane.

Dear Sirs,

Here we acknowledge with thanks for your enquiry for **"ELEPHANT MHE"** make Single Girder EOT Cranes Modifications. We are submitting herewith our best offer for your kind consideration.

With reference to above and based on the technical specification provided by you, we herewith give you our best offer as per the below annexure for your kind consideration.

Annexure – I	:	Price Schedule
Annexure – II	:	Technical Specifications
Annexure – III	:	Terms & Conditions

We look forward to receive your valuable and favorable feedback in the above matter at the earliest.
Thanking You,

Yours faithfully,

For ELEPHAMNT MATERIAL HANDLING EQUIPMENTS

Mr. Rahul Deshmukh
Mobil No. +91 8888875338
Mail Id :- ***sales@elephantmhe.com***
Web:- www.elephantmhe.com and www.indiamart.com/elephantmaterialhandling

Address:-
Office: Plot No-07, Nirvan Enclave,
Sector No-07, Bhosari MIDC, Pune.
Works: Gate No-1231, Sonvane Wasti,
Talwade, Pune.





ELEPHANT

Annexure – I – **PRICE SCHEDULE.**

<table>
<tr>
<td>1 A</td>
<td>
<u>Single Girder E. O. T. Crane:</u> MODULER TYPE CRANE

“ELEPHANT MHE” make 5MT x5.0 M SPAN SINGLE GIRDER, Floor operated type Goliath E. O. T. Crane.
<table>
<tr><td>Safe Working Load</td><td>5.0 MT</td></tr>
<tr><td>Span</td><td>10.0 Mtr</td></tr>
<tr><td>Class of Duty</td><td>Class II as per IS 807/3177</td></tr>
<tr><td>Operation</td><td>From Floor Through Pendant Push Button Control</td></tr>
<tr><td>Location</td><td>Indoor</td></tr>
<tr><td>Height of Lift</td><td>05 Mtr</td></tr>
<tr><td>Main Hoisting Speed</td><td>3.0 m/min Micro motion Through Duel Speed Motor / VFD</td></tr>
<tr><td>Cross Travel Speed</td><td>12.0 m/min Micro motion Through Duel Speed Motor / VFD</td></tr>
<tr><td>Long Travel Speed</td><td>18.0 m/min Micro motion Through Duel Speed Motor / VFD</td></tr>
<tr><td>Main Hoist Motor Rating</td><td>4.0 KW</td></tr>
<tr><td>Cross Travel Motor Rating</td><td>0.37 KW</td></tr>
<tr><td>Long Travel Motor Rating</td><td>0.55 KWX 2 NoS.</td></tr>
<tr><td>All Motors Type</td><td>Sqr.cage, Crane Duty Motors, 40% CDF, 150 Sts/hr, make SEW / ABM / NORD / Bauer / BONFIGLOLI / MGM-i-MAK MAKE</td></tr>
<tr><td>Main Hoist, Cross Travel & Long Travel Brake Type</td><td>Inbuilt D.c disc tpye.</td></tr>
<tr><td>Main Hoist Wire Rope Diameter</td><td>10 mm</td></tr>
<tr><td>Main Hoist Number of Falls</td><td>4 fall</td></tr>
<tr><td>Wire Rope Construction</td><td>6 x 36, FMC, 2160 N/mm^2 UTS</td></tr>
<tr><td>Cross Travel Wheel Diameter</td><td>125 mm x 4 Nos.</td></tr>
<tr><td>Long Travel Wheel Diameter</td><td>160 mm x 04 Nos.</td></tr>
<tr><td>All Wheels</td><td>Double flanged, Live Axle Execution</td></tr>
<tr><td>Hook</td><td>Single shank, forged as per IS 3815, Swiveling type</td></tr>
<tr><td>Crane LEG Both Side</td><td>RIGID type</td></tr>
<tr><td>Long Traverse wheel load without impact</td><td>3.0 MT</td></tr>
<tr><td>Total Crane weight approx.</td><td>3.7 MT</td></tr>
<tr><td>Limit Switches (Hoisting / Cross Traverse / Long Traverse)</td><td>Included</td></tr>
<tr><td>Rubber Buffer on Long Traverse</td><td>Included</td></tr>
<tr><td>Power / Control Voltage</td><td>415V, 3Phase, 50Hz / 110V, 1Ph, 50HZ</td></tr>
<tr><td>DSL Type</td><td>Shrouded Bus Bars (Quoted extra)</td></tr>
<tr><td>Painting</td><td>1coat of Grey oxide primer and Golden yellow enamel colour</td></tr>
</table>
</td>
<td>01 No.</td>
<td>6,90 ,000.00</td>
</tr>
<tr>
<td>1 B</td>
<td><u>Power Feeding Arrangement :</u>

Cable Drum type, electromagnet operated cabling drum for crane power supply</td>
<td>PerSet</td>
<td>35,000.00</td>
</tr>
<tr>
<td>1 D</td>
<td><u>Charges for Erection & Commission</u>:
Erection & Commissioning Charges for above Cranes and DSL Busbar System (For installation mobile crane on site at your scope)</td>
<td>1 Job</td>
<td>30000.00</td>
</tr>
</table>

Annexure – II Technical Specification for E. O. T. Crane

Sr. No.	Items	Material / Make
1	Main Girders IS – 807	Double Girder – Box type fabricated from plates IS – 2062. Essar / Sail make
2	End carriages	Plate type - Box type fabricated from plates IS – 2062. Essar / Sail make
3	Geared Motor	ABM / SEW / NORD / BONFIGLOLI / MGM Make
4	C. T. / L. T. Wheels	En-8 (Hardness will be 250 to 300 BHN) All wheels are machined & Forged material.
5	VVF Drive	Schneider Make / L&T / Yasakawa
6	Brakes	Electro Magnetic DC Brake in built,
7	Bearings	Anti-friction type Roller Ball Bearing – FAG make & in wheels URB/ ZKL
8	Wire rope drum	Seamless Pipe
9	Wire rope	Usha Martin make (6 x 36) FMC
10	Hook	As per IS 3815 duly tested.
11	Contactors, Relay, Fuses, Main Contactor	Siemens make, or equivalent
12	Limit Switches	Speed O Control / TOP make or equivalent, 2 Way Roller type Limit Switch in C. T. & L. T.
13	Push Button	Gieoyanzava/ TER Etaly Make, two step Push Button.
14	Power cable	Flexible cable - ISI make
15	G. A. Drawings	Detailed dimension drawings will be submitted to you for your approval after the order confirmation.

Annexure – III

Items	Terms & Condition
Prices	The above prices quoted are ex-works Bhosary, Pune
TAXES	GSTIN 18% Applicable
P & F	1.5% will be charged extra (if applicable). NIL
Delivery	4 – 5 weeks staggered delivery from the date of receipt of your confirmed Purchase Order along with advance payment.
Erection & Commission	2 to 3 week after site clearance conformation. (1 Job)
Payment Terms	40% advance along with P. O., 60% prior to dispatch against proforma invoice / at the time of inspection at our works by your representative and 50% erection charges to before starting and remaining 50% immediately after completion of erection work at your site.
Transportation	Transportation will be in your scope.
Validity	Offer is valid for 21 days
Overdue Interest & Warehousing charges:	If your ordered goods are not lifted after 2 week of delivery date mentioned in the P.O./Our order confirmation, 2% (of order value) per week will be charged being Overdue Interest & Warehousing charges.
Load Testing	We can provide load test at your site only, you will have to arrange the load under the said crane along with respective Sling.

Annexure – III Continue…

Insurance	The Purchaser is advised to insure the goods to cover transit risks of all kind. If required insurance can also be arranged by us on behalf of the buyer at extra cost, on actual provided the same is also stipulated in the order. However whether the insurance is effected by the buyer or arranged by us on behalf of the buyer our liability shall cease from the moment the goods are handed over to the buyer or his nominee or to the carrier arranged by us on behalf of the buyer. In the event of any damage in transits including during loading / unloading of shortages, the buyer shall lodge the claim with the insurance company directly and also comply with the claim formalities.
Liquidated Damages & Force Majeure Clause	We have given our delivery schedule in good faith & will try schedule. In case of delay in delivery of the Equipment concerned, we are no agreeable for payment of liquidated damages or any penalty. We are also not agreeable for any risk purchase by you. For such delays, we shall not be liable to any claim or for any compensation
Warranty	Warrantee shall be valid for the period of **12 months(1 Year)** from the date of dispatch. We hereby Warrantee to replace free of cost Ex-works Kathwada; any component found defective due to bad workmanship or any Manufacturing defects only. No Warrantee provided for electrical Components. (If any electrical failure occurs and due to this if any Mechanical component fails than the same shall not cover any Warrantee and the same will be supplied only on chargeable basis.)
Cancellation	An order once placed by the buyer cannot be cancelled without the prior consent in writing from us. In the event of our accepting the cancellation, all costs incurred by us till our acceptance of cancellation will be borne by the buyer
Documentation provided during delivery	Company Certificate : (a) Test Certificate & (b) Warrentee Certificate 2) Test Certificate of : (a) Motors, (b) Wire Rope & (c) Hook 3) Complete Manual of Crane will be provided with sub assembly for Hoisting & C. T. Gear Boxes, Bottom hook, Electric diagram etc.

Should you require any further techno – commercial information, please feel free to contact us.

Thanking you.

Yours truly,

For ELEPHAMNT MATERIAL HANDLING EQUIPMENTS

Mr. Rahul Deshmukh
Mobil No. +91 8888875338
Mail Id :- ***sales@elephantmhe.com***
Web:- www.elephantmhe.com and www.indiamart.com/elephantmaterialhandling

Address:-
Office: Plot No-07, Nirvan Enclave,
Sector No-07, Bhosari MIDC, Pune.
Works: Gate No-1231, Sonvane Wasti,
Talwade, Pune.



