INTERWAL WORK ORDER

Client:		**PO Number:**	22230170	**W. O. No-**	SO/22-23/078
Cloos India Welding Technology Pvt Ltd		**PO Dated :**	3/13/2023	**W. O. Date**	3/14/2023
Address:		**PO Received Date:**	3/13/2023	**Sales Co ordinator**	Shailesh
Ground and First Floor, Plot No 114/1/3, MIDC, General Block, Bhosari - 411026		**Ref. Quotation:**	SQA.22.23.0366R4	**Front Sales Person**	

Dispatch Address:

JCB Industries Private Limited
GIDC Halol 2, Plot No 699 to 703,
Maswad Industrial Estate, Halol,
Dist - Panchmahal, Gujarat - 389350

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Motorized 3 Leaf Telescopic Sliding Gate W6000 mm X H1800 mm**	**Sheet 2**	**Nos**	**4**			**0**	**Pending**
						Total	**0**	

Non standard items/extra requirement, if any:

B Commerical Terms:

1	**Payment Terms:**	40% Advance of basic amount immediately after release of PO, 40% + full taxes at the time of dispatch and inspection at suppliers place and balance 20% to be released after successful trails completion of work on site with final sign off.		
2A	**Delivery Date as per PO:**	4 - 5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.	2B. Required Delivery Date:	
3A	**Transportation Scope:**	Extra at actual	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NA		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	AGM	SALES	Operation	PROJECT	DESIGN	Date & Time
Mr. Ameet Kurhade		**Mr. Shailesh**	**Mr. Kiran M**	**Mr. Sandeep M**	**Mrs. Nirmala**	**20/03/2023**

Motorized 3 Leaf Telescopic Sliding Gate with vision window (each Leaf)

Sr .No.	Specification	Telescopic Sliding Gate
1	**Door type**	Motorised Three Leaf Telescopic Sliding Gate
2	**Clear Opening gate**	(W) 6000 mm X (H) 1800 mm
3	**Master Leaf Size**	2670 X 1800 mm
4	**1 ST Leaf Size**	2370 X 1800 mm
5	**2 ND Leaf Size**	2370 X 1800 mm
6	**Opening Direction**	Horizontal - from left to right or reverse
7	**Mounting Location area**	Inside area
8	**Design Pattern**	Standard Tubular Design Pattern
9	**Outer Frame Tube Sizes**	50 X 50 X 3 mm MS SHS
10	**Internal Vertical Tube**	50 X 25 X 3 mm MS SHS
11	**For Post**	50 X 50 X 3 mm MS SHS
12	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
13	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings
14	**Guide Rollers supporter**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of
15	**Painting**	Powder Coating
16	**Control Panel**	1 No Operating Station.
17	**Operation**	By Telescopic Mechanism
18	**Accessories**	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4. Hooter
		5. Photocell
19	**Civil work**	Client scope – client need to grout the I beam in concrete to create track for sliding gate