NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

KUNAL HOUSEWARES PVT. LTD.
15/16 Manor Palghar road,
Netali Village, Palghar 401 404

Date : 09.06.2021
Quote NO : **MHE_21.22.0012**
Kind Attn : Mr. K.K. Sreekanth
Email Id : mnt1@khpl.in
Contact No: 9987183408

Project Name & Location: Telescopic Truck Loader/Unloader Conveyor, Faridabad

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering 03 people for 03 days in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor (Width Of Conveyor Belt : 600 mm)**	1	13,46,400	13,46,400	75,000	75,000
2	**Telescopic Conveyor (Width Of Conveyor Belt : 800 mm)**	1	15,85,920	15,85,920	75,000	75,000
		Total		29,32,320		1,50,000
	P&F Charges	3%		87,970		
	Total Without Taxes			30,20,290		1,50,000
	GST Extra @ 18%	18%		5,43,652		27,000
	Total With Taxes			35,63,942		1,77,000
3	Transportation Charges					Extra At Actual
4	Insurance					Extra At Actual
5	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Collapsed Length	6000 mm
2	Telescopic Length	10500 mm
3	Total Length	16500 mm
4	No. of Extension Stages	3
5	Belt Width	600 mm & 800 mm
6	Belt Speed	30 mtr/min with (Variable through VFD)
7	Belt Direction	Bi-directional for loading and unloading
8	Power Supply	240 VAC, 50 Hz
9	Load Capacity	50 Kg/mtr

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd