NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

**Sales Quotation**

**Quotation No - SQT/19-20/1812** **Date :15.07.2019**

Miven Mayfran Conveyors Pvt Ltd.
Hubli, India.

**Kind Attn:** Mr. Chandrashekhar Kori
**Email:** ckori@mivenmayfran.com
**Contact No:** 9008488962

**Project Name And Location : Miven Mayfran Conveyors Pvt Ltd , Hubli.**

**Subject :** Quotation for Pick and Place Machine

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

**Commercial Offer**

| Sr. No. | Description | Qty | Unit | Rate In INR | Net Amount INR |
|---|---|---|---|---|---|
| **A** | **Pick and Place Machine**<br>**( Supply + Installation )** | | | | |
| 1 | X axis travel: 4000 mm<br>Z axis Travel: 1600 mm<br>Structure height : 2600 mm<br>Capacity : 20 kg<br>Gripper Type: Pneumatically Control<br>Gripper Size: D25 x 350 mm<br>Control: Automatic & manual ( through operating panel)<br>Control Feature :<br>• In Auto Mode operation will be done in predefine sequence programmed through PLC control module<br>• In manual mode operation of each link can be controlled through operation panel | 1 | No | 2,400,000 | 2,400,000 |
| | | | | **Total** | 2,400,000 |
| | | | | | |
| **B** | **Two axis Gantry**<br>**( Supply + Installation )** | | | | |
| 1 | X & B Axis Pick & place<br>X Axis travel : 500 mm<br>B axis Radius : 1200 mm<br>Base Structure height : 600 mm<br>Primary Arm : 1500 mm<br>Secondary Arm : 850 mm<br>Capacity: 15kg<br>Gripper type : Electrical & Pneumatic Control<br>Control : Automatic & manual ( through HMI panel)<br>Control Feature :<br>• In Auto Mode operation will be done in predefine sequence programmed through PLC control module<br>• In manual mode operation of each link can be controlled through HMI panel | 1 | No | 2,300,000 | 2,300,000 |
| | | | | **Total** | 2,300,000 |

| | | | |
|---|---|---|---|
| **GST Pune** | 27AAECN0437H1ZM | **TOTAL BASIC AMOUNT** | **4,700,000** |

**General Prerequisites Required at Site**

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

**Limit of Supply**

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

**Quote/Supply is based on**

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities
3. Billing will be as per the supply of material ,not as per site measurements

**The supply included only those mentioned in the quote & does not include**

1. Unloading from truck placement on site
2. Electrical connection for control panel.

**Client Scope**

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

**Terms and Conditions :**

| | | | |
|---|---|---|---|
| 1 | **Price** | : | Ex. Works Pune |
| 2 | **P & F Charges** | : | @3% of Total Supply Value |
| 3 | **Freight Notes** | : | Extra as applicable + Taxes |
| 4 | **Delivery** | : | 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment, |
| 5 | **Payment** | : | 80% Advance along with Confirmed Purchase Order and Balance before Dispatch. |
| 6 | **Insurance** | : | Extra As applicable |
| 7 | **Taxes** | : | GST Extra as applicable |
| 9 | **Validity** | : | Validity of Offer is 15 days from the date of quotation |
| 10 | **Warranty** | : | 12 months from the date of supply. |

Please feel free to contact **Mr.Arjun Patil - 8551096333** For any further Clarification /Information in this concern.

With Best Regards

Pradip
7709586333

For NIHVA Technologies Pvt Ltd