WORK ORDER

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Client
M A Engineering

PO Number:		MAE/217/20-21	W. O. no-	SO/20-21/039
PO Dated :		01-Oct-20	W. O. Date	03.10.2020
PO Received Date:		02-Oct-20	Sales Co ordinator	Varsha
Ref. Quotation:		SQT/20-21/2413R	Front Sales Person	Arjun

Dispatch Address:

John Deere India Pvt Ltd
Sanaswadi, Pune

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply	Installation	Amount	Dwg. Approval
1	Motorised Double wall rolling shutter	Size : (W)5000 x (H)4500 mm	NO	1		-	-	Pending
			Total	1			-	

Sr. No	Description	Details
		Motorised Double wall rolling shutter
1	Size	Size : (W)5000 x (H)4500 mm
2	Insulation material	Shutter filled with 20 mm thick PU Form
3	Side Frames	Aluminium Guide rails with blackplastic runner
4	Wind load	class 3 (EN 12424)
5	Bottom profile	Aluminium extruded, Double Skinned
6	Power input	1 phase current 0.25kW
7	Protection	IP 65
8	No of Cycles	10 Cycles/hour
9	Control	Integrated microprocessor control along with operator
10	Vision panel	4 rows of Vision panel

A) Commerical Terms

1)	Payment Terms:	50% advance and Balance pay 30days from reciept of material
2)	Delivery Date as per PO:	26th Oct 2020
3)	Transportation:	Inclusive
4)	P&F Charges:	nil
5)	Loading:	NIHVA
6)	Unloading:	NIHVA
7)	Lifting Equipments:	NIHVA
8)	Warranty:	1 year from date of Installation
9)	Height arrangement:	NIHVA
10)	Electricity Supply:	Client
11)	GST:	18% Extra
12)	Installation Scope:	NIHVA
13)	Mode of import:	NA
14)	HSS:	NA
15)	Documentation Required:	Standard Handover Documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT		PPC	DESIGN	Date & Time
A. K.	A. P.	S. P.		S.B.	P. A.	