NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1295AR **Date : 09- 08-2019**

Ratnarup Projects Pvt. Ltd.,
Baner
Pune

Kind Attn: Mr. Nilesh
Email: purchase@ratnarupprojects.com
Contact: 9657859393

Project Name And Location : Stihl, Chakan, M.I.D.C., Phase-3 site.

Subject : Quotation for Sectional Door.

Dear Sir
Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty.	Unit	Rate In INR	Net Amount INR
	ASSA ABLOY - Sectional door **(100% Imported products from Europe) OH 1042P** **This Includes -** **• Track type: Standard Lift,** **• 2 Vision Windows,** **• Motor & control,** **• Bottom safety edge (Pneumatic Safety Edge)** **• Manual Operation: Pull down rope and step/lifting handle** **•Safety: Spring Break Device** **(Supply + Installation)**				
1	**Size : (W) 3000 mm x (L) 4000 mm**	8	No	341,000	2,728,000
	Optional Accessories				
1	**Additional Operating Switch from other side of opening**	1	No	6,500	6,500
2	**Microwave radar- Single side**	1	No	18,500	18,500
3	**Microwave radar- Both side**	1	No	21,500	21,500
4	**Magnetic Loop Detector- Single Side**	1	No	18,500	18,500
5	**Magnetic Loop Detector- Both Side**	1	No	21,500	21,500
6	**Remote control with receiver**	1	No	5,000	5,000
7	**Remote control Hand Unit**	1	No	8,500	8,500
8	**Pull cord- Single Side**	1	No	8,500	8,500
9	**Pull Cord- Both Side**	1	No	17,000	17,000
10	**Magnetic Radar - Single Side**	1	No	NA	NA
11	**Magnetic Radar - Both Side**	1	No	NA	NA
12	**Hand chain for manual operation**	1	No	9,500	9,500
13	**Key Switch**	1	No	NA	NA
14	**Advance frequency convertor control for speed adjustment**	1	No	NA	NA
15	**Safety Photocell**	1	No	8,500	8,500
16	**Optical wired safety edge sensor at bottom edge**	1	No	NA	NA
17	**Optical wireless safety edge sensor at bottom edge**	1	No	NA	NA
18	**Flashing Light**	1	No	12,500	12,500
19	**Fixed Bollards**	1	No	5,500	5,500
20	**Vision Panel for Full width**	1	No	35,000	35,000
21	**Vision windows**	1	No	12,000	12,000

GST Pune:	27AAECN0437H1ZM

Total	**2,728,000**

Sr .No.	Specification	Crawford - NIHVA Assaabloy	
1	Door type	1042P	
2	Clear Opening dimension	(W)3000 x (H) 4000 mm	
3	Opening Direction	Standard	
4	Type of Mounting	Standard	
5	Door produced Based on which certificatio	Doors produced according to ISO 9000 or ISO 14000 certified	
6	Opening/Closing Speed	0.25 m/s	
7	**Door Material**	GI Steel with PUF inside	
8	Panel Thickness	42mm	
9	Panel colour	RAL 9002 Powder coated	
10	External surface of the panel	diamond grid design with a glossy finish at the section joints.	
11	inside surface of the panel	Monolithic surface on the inside of the door	
12	Broken cold bridge	Section joints with broken cold bridges	
13	Door sealent	All door sealants made of EPDM rubber.	
14	All Panel height	All panels should be 545mm high	
15	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.	
16	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.	
17	Steel component Material	All steel components to be electro galvanized	
18	Hinge Material	Glass fibre reinforced Polyamide	
19	Panel Thickness	42 mm	
20	Spring Material surface finish	Powder coated	
21			
22	Water Penetration	EN 12425	class 3
23	Air Permealibity	EN12426	class 2
24	Wind Load	EN21424	class 3
25	Thermal Transittance	EN 12428 1.10W /m2K	
26	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
27	Door saftey device 1	Doors equiped with spring break device	
28	Door saftey device 2	Door equiped with pneumatic safety edge	
29	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	
30	Incase of Power failuer	One can operate the Door manually	
31	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
32	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft	
33	Emergency Operation	by Disengagement rope manual	
34	Operating Switch	Up/Down Keypad + stopbutton	
35	Environmental Green Product Declaration Certification	as per ISO 14025 and EN 15804	

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry / structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provide structure drawing only if required
5. Existing / Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8 -9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @ 18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on7219207333 For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti.

7219206333

For NIHVA Technologies Pvt Ltd