NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1138 **Date : 10-01-2019**

Jones Lang LaSalle Property Consultants (India) Pvt. Ltd
Level 16 Tower C Epitome Building no 5
Level 16 Tower C Epitome Building no 5
DLF Cyber city Phase III, Gurugram 122002

Kind Attn : Mr. Punit Jain
Email : Punit.Jain@ap.jll.com
Contact No : 8058928484

Project Name And Location : Embassy Project

Subject : Quotation for Motorised Rolling Shutter & Geared Rolling Shutter

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **GI Slat:1 mm Thk, Curved Type Profile with heavy duty Shaft, Guide, Hood Cover 0.9 mm thick, Motor - Indirect Drive, inclusive of painting** **Supply + Installation + Transportation + Loading**				
1	Size : (W) 2500 mm x (H) 3000 mm	150	No	76,000	11,400,000
2	Size : (W) 4000 mm x (H) 5000 mm	15	No	129,000	1,935,000
B	**Gear Operated Rolling Shutter** **GI Slat:1 mm Thk, Curved Type Profile with heavy duty Shaft, Guide, Hood Cover 0.9 mm thick, Gear Assembly, inclusive of painting** **Supply + Installation + Transportation + Loading**				
1	Size : (W) 2500 mm x (H) 3000 mm	100	No	59,000	5,900,000
2	Size : (W) 4000 mm x (H) 5000 mm	5	No	115,000	575,000

GST Pune	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in - NIHVA scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	@ Site
2	**P & F Charges**	:	Nil
3	**Freight Notes**	:	Inclusive
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance and Balance Before dispatach
6	**Insurance**	:	Extra as applicable
7	**Tax**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 08551096333** For any further Clarification / Information in this Concern.

With Best Regards

Varsha
8551091333
For NIHVA Technologies Pvt Ltd