NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Arcelor Mittal Nippon Steel India Ltd
Pune

Date : 13.05.2022
Tender Document. No AMNS/PUN/720-PCS/0322-05/263473
Quote No : RR_21.22.0127R2
Kind Attn : Mr. Sumeet Khamgaonkar
Email Id : Sumeet.Khamgaonkar@amns.in
Contact No: 84829 37013

Project Name & Location: Arcelor Mittal Nippon Steel India Ltd, Pune

Subject : Techno-Commercial Offer for Supply & Fixing of Canopy

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Supply & Fixing of Canopy for all the Four Lines At Arcelor Mittal Nippon Steel India Ltd, Pune** • CRS Line: W-5.4mtr, L-32mtr, H-4.4mtr • CRNCTL Line: W-4.4mtr, L-30mtr, H-4.4mtr • CRWCTL Line: W-5.4mtr, L-45mtr, H-4.4mtr • Trap Line: W-6.23mtr, L-45mtr, H-4.4mtr • Dismantling of existing canopy at CR lines • Provision for Lighting arrangement	**1**	**77,85,000**	**77,85,000**	**1,95,000**	**1,95,000**
	Total Without Taxes			**77,85,000**		**1,95,000**
	GST Extra @ 18%		18%			**Extra At Actual**
	P&F Charges @ 3%		3%			**Extra At Actual**
	FOT and FOR for Pune location					**Included**
	Unloading Charges @ Site					**Included**

B) Technical Specification

1. Glazing : Polycarbonate Compact Clear 4.0 mm Thick
2. MS Column SHS 100 x 100 x 4
3. MS Beam SHS 72 x 72 x 4
4. MS Base plate 400 x 400 x 10
5. MS Frame Section 50 x 50 x 3
6. MS Junction Plate 300 x 300
7. MS Hook for removing provision
8. MS intermediate support section 25 x 25 x 2
9. Manual locking to the structure of each panel
10. Interlocking arrangement between the panels
11. Rust preventive Fasteners
12. Surface finish - Primer epoxy paint, 100 micron

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component.
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope.

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required.	In Client Scope

D) Terms & Conditions

Price :	Ex Works Pune.
Delivery :	14-15 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
Payment :	60% Advance along with Confirmed Purchase Order. 35% Along with Approval of Drawing and before start a Production. 5% Against completion of Installation, Testing and Commissioning.
Validity :	Validity of Offer is 15 days from the date of quotation.
Warranty :	12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.
Design Clause :	NIHVA shall be deemed the authors of their respective concept and drawings with reserved rights, including copyrights. It shall not be used by the owner for future additions or alterations to this Project or for another project or should not copied at any other future project or should not transfer or copied by anyone.
Compensation Clause :	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd