NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/0967R **Date : 28-11-2018**

Aegis Infra Solutions
No. C - 15, Shah Complex - 1, Palm
Beach Road Sector- 13, Sanpada
Navi Mumbai -400705

Kind Attn: Mr. Balmukund Sharma
Email: mukund@aegisinfra.in
Contact No : 8691028888

Project Name And Location :

Subject : Quotation for Dock Leveller
Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Dock Levelers (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers**				
1	**Dock Levelers Capacity 9 Ton** Size : (W) 2500 mm X (H) 3000 mm Supply + Installation	1	No	239,000	239,000
				Total	**239,000**

GST Pune	27AAECN0437H1ZM	**Grand Total**	**239,000**

Technical Specifications for NIHVA Make Dock Leveller – 9 Ton

Sr. No.	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	4 Ft
6	Travel above & below dock level	(+) 300 / (-) 200 mm
7	Platform Size (W x L)	**2500 mm x 3000 mm**
8	Lip size (W x L)	2500 x 400 mm
9	Dock Leveller (Shut) Height	480 mm
11	Overall length	2500mm x 3000mm + Lip Length (400mm)
12	Deck Plate (MS Chequered)	8 mm Thick
13	Lip Plate	16 mm Thick
14	Maximum slope can be achieved	10%
15	Clear Pit dimensions (W x L x D)	(W) 2550 mm x (L) 3050 mm x (D) 485 mm
16	Driver type	Direct by electric Motor
17	**Motor Ratings & Control Pannel**	**1 H.P Motor - Flame Proof**
18	Pump design flow	2.8 LPM
19	Pump pressure	120 bar Operating 200 bar Max.
20	Safety valve set pressure	120 Kg/cm²
21	Pump Type	Gear
22	No Of Deck cylinder	2 Nos
23	Lip Cylinder	1 No
24	Dock Bumper	Included - 1 pair

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Nil
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment and Drawing approval.
5	**Payment**	:	50% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on 8551096**333** For any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd