NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mr. Rajesh Narayan
Banaglore

Date : 10.12.2021
Quote NO : RR_21.22.0133
Kind Attn : Mr. Rajesh Narayan
Email Id : md@igicorp.in
Contact No: 9980198000

Project Name & Location: Mr. Rajesh Narayan, Bangalore

Subject : Commercial Offer for Automatic Rotating Al.Louvers

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size (mm)	Qty	Supply and Installation Charges in INR	
			(Nos)	Unit Price	Total Amount
1	**Automatic Rotating Al. Louvers**	• *5300 X 6900 mm* • *LED Light* • *Installation Inclusive*	1	10,00,000	10,00,000
			Total		**10,00,000**
2	GST Extra @ 18%				**Extra At Actual**
3	P&F Charges @ 3%				**Extra At Actual**
4	Transportation Charges				**Included**
5	Unloading Charges @ Site				**In Client Scope**

B) Technical Specification

Automatic Rotating Al. Louvers

1. Material-Aluminium alloy 6005 T5
2. Color finish is Anthracite Grey RAL 7016
3. U shape drain water gutters and hide downpipe
4. IP67 waterproof motor and remote control system, motor inside of aluminum beam design
5. Accessories material in stainless steel 304 and brass H59

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which will cost you extra.
12. It only covers damage caused due to mechanical system not due to natural calamity.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price :	Ex Works Pune.
Delivery :	6-8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
Payment :	80% Advance along with Confirmed Purchase Order. 20% Against Material Delivery.
Validity :	Validity of Offer is 15 days from the date of quotation.
Warranty :	12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd