NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0057 **Date : 06-10-2017**

InnoVen Chem LLP
A7/5, Kripa Industrial Complex,
village Sonale Mumbai Nashik Highway
NH3, Ta Bhiwandi Thane- 421302

Kind Attn: Uday C Somaiya
Email: uday@innovenchem.in
Contact No : 94230 12992

Subject : Quotation for Dock Leveller

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer :-

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**Dock Levelers (6 Ton)** **Size : (L) 2720mm X (W) 2030mm x (H)480mm**	2	No	1,95,000	3,90,000
2	Installation charges for above Dock Leveller	2	No	20,000	40,000
	Total				**4,30,000**

HSN code for Dock Leveler	**84289090**
GST Pune	**27AAECN0437H1ZM**

Amount in words:	**Rupees Four Lacs Thirty Thousand only**

Technical Specification :-

Sr. No.	Description	Specifications
1	**Product**	**Dock Levelers**
2	**Make**	**Nihva**
3	Capacity	6 Ton
4	Dock operation mode	AC power pack hydraulically operated
5	Lip operation mode	Hydraulic
6	Operation control	Through panel
7	Loading platform height from road	1250mm
8	Travel above & below dock level	(+) 300 / (-) 150 mm
9	Platform Size (W x L)	2000 mm x 2720 mm
10	Lip size (W x L)	2000 x 400 mm
11	Shut Height	480 mm
12	Working length	2720 mm
13	Overall length	2000mm + Lip Length (400mm)
14	Maximum slope can be achieved	10 deg
15	Clear Pit dimensions (W x L x D)	(W) 2030mm x (L) 2720 mm x (D) 480 mm
16	Hydraulic power pack	Standard
17	Driver type	Direct by electric Motor
18	Motor Ratings	1 H.P
19	Pump design flow	2.5 LPM
20	Pump pressure	120 bar Operating 200 bar Max.
21	Cyllinder working Pressure	100-120 Bar
22	Max Force applied by Cyllinder	12.5 KN
23	Bore of Cyllinder	40mm
24	Stroke of Cyllinder	320m
25	Safety valve set pressure	120 Kg/cm²
26	Pump Type	Gear
27	Volume of oil receiver	7 Lit
28	No Of Deck cylinder	2 No
29	Lip Cylinder	1 No
30	Dock Bumper	Included

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. All structure support is in client scope
3. NIHVA Will provided structure drawing only if required
4. Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Thane
2	**P & F Charges**	:	Extra @3%
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST@28% on Supply GST@ 18% on Installation
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Mayur Derle** on **07709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd