Sales Quotation

Quotation No - SQT/19-20/1682 **Date : 5.06.2019**

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,,
M.I.D.C., Baramati, - 413133
Maharashtra, India

Kind Attn: Ms. Minal Surve
Email: Minal.SURVE@ferrero.com
Contact No: 2112662351

Subject: Quotation for High speed Door RR300+ Alu, Steel Door

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Unit Rate INR	Total Rate INR
A	**Albany Make Rapid Roll Up Door RR300+AL (100% Imported with all components – made in Germany)**				
Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.				
Barrel:	Aluminium, anodized with shafts made of galvanized steel				
Wind Reinforcement:	Door Panel wind tabs for improved wind resistance				
Side Frames:	Aluminium profiles, anodised				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.				
Bottom beam:	Anodized extruded aluminium.				
Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s				
Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns				
1	**Size: (W) 3000mm X (H) 4000 mm**	1	No	650,000	650000
2	Installation of above door	1	No	20,000	20000
B	**Non Fire rated Door with Rockwool Infill .GI Sheet Doors panel with 46mm thk & 0.8 mm Face Sheet.Frame 1.2mm thk. and 100X57mm Jamb depth & width**				
1	**Single Leaf Door (Supply + Installation)** **Size : (W) 1000 mm x (H) 2200 mm** • SS Ball Bearing Hinge 102X76X3mm • Door Closer • Dead Lock • Anchor Fastener • Cylinder with one side key & other side turn bolt On Rose (80mm)SS • Both Side SS Pull Handle, D Type (300mm X 22mm dia.) • Vision Panel - 300 x 200 mm	1	No's	33,000	33,000

GST Pune	27AAECN0437H1ZM

Grand Total	**703,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	10-11 weeks for HSD & 4-5 Weeks for Steel Door from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra @ actual
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on 8551096333 For any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd