**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**SUROJ BUILDCON PVT. LTD.**
Bungalow No. 3, Liberty Society Phase-I, North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

**Project, Location : Shabad, Ranga Reddy District in Telangana.**

**Date :** 10.03.2021
**Quote NO :** SQT.20.21.3093
**Kind Attn :** Mr. Subodh Bhosale
**Email Id :** sbhosale@suroj.in
**Contact No:** 7058078520

**Subject : Quotation for High Speed Door , Boom Barrier , Dock Leveler & Single Skin Galvalume Rolling Shutters**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 To 5 |
| C. | General Conditions | 6 |
| D. | Terms & Condtions | 6 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Single Skin Motorised Rolling Shutter** | 3500 | 4500 | 1 | 125,000 | 125,000 | 20,000 | 20,000 |
| 2 | **Single Skin Motorised Rolling Shutter** | 3500 | 5000 | 1 | 140,000 | 140,000 | 20,000 | 20,000 |
| 3 | **Single Skin Motorised Rolling Shutter** | 2500 | 4500 | 1 | 105,000 | 105,000 | 20,000 | 20,000 |
| 4 | **Single Skin Motorised Rolling Shutter** | 3000 | 3000 | 1 | 95,000 | 95,000 | 20,000 | 20,000 |
| 5 | **Single Skin Motorised Rolling Shutter** | 6000 | 6000 | 1 | 230,000 | 230,000 | 20,000 | 20,000 |
| 6 | **Single Skin Motorised Rolling Shutter with Partly Grill -600 mm** | 3500 | 4500 | 1 | 130,000 | 130,000 | 20,000 | 20,000 |
| 7 | **Single Skin Motorised Rolling Shutter with Partly Grill -600 mm** | 3500 | 5000 | 1 | 145,000 | 145,000 | 20,000 | 20,000 |
| 8 | **Single Skin Motorised Rolling Shutter with Partly Grill -600 mm** | 2500 | 4500 | 1 | 110,000 | 110,000 | 20,000 | 20,000 |
| 9 | **Single Skin Motorised Rolling Shutter with Partly Grill -600 mm** | 3000 | 3000 | 1 | 100,000 | 100,000 | 20,000 | 20,000 |
| 10 | **Single Skin Motorised Rolling Shutter with Partly Grill -600 mm** | 6000 | 6000 | 1 | 235,000 | 235,000 | 20,000 | 20,000 |
| 11 | **RAPID ROLL-UP DOOR** | 2500 | 4500 | 15 | 325,000 | 4,875,000 | 20,000 | 300,000 |
| 12 | **RAPID ROLL-UP DOOR** | 3500 | 4500 | 25 | 340,000 | 8,500,000 | 20,000 | 500,000 |
| 13 | **RAPID ROLL-UP DOOR** | 3500 | 5000 | 20 | 350,000 | 7,000,000 | 20,000 | 400,000 |
| 14 | **RAPID ROLL-UP DOOR** | 3000 | 3000 | 22 | 290,000 | 6,380,000 | 20,000 | 440,000 |
| 15 | **Dock Leveler - 15 Ton UDL** | 2000 | 2500 | 50 | 190,000 | 9,500,000 | 20,000 | 1,000,000 |
| 16 | **Boom Barrier - 5 Mtr** | 5 Meter | | 25 | 90,000 | 2,250,000 | 10,000 | 250,000 |
| 17 | **Boom Barrier - 8 Mtr** | 8 Meter | | 50 | 125,000 | 6,250,000 | 10,000 | 500,000 |
| | **Total** | | | **217** | | **46,170,000** | | **3,590,000** |
| | P&F Charges | | | 3% | | 1,385,100 | | |
| | **Total Without Taxes** | | | | | 47,555,100 | | 3,590,000 |
| | GST Extra @ 18% | | | 18% | | 8,559,918 | | 646,200 |
| | **Total With Taxes** | | | | | **56,115,018** | | **4,236,200** |
| | Transportation Charges | | | | | **Extra at atcual** | | |
| | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**RAPID ROLL-UP DOOR**



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Use | Internal Door |
| 2 | Speed | Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking |
| 3 | Opening / Closing speed | Opening / Closing speed 0.8 m/s. |
| 4 | Control Panel | 4 Push Button operated |
| 5 | Resistance to wind load | EN12424 upto class 2 |
| 6 | Curtain | Fabric Transparent PVC section |
| 7 | Curtain colour | Standard blue RAL 5010 |
| 7 | Guide Material | Galvanised steel. |
| 8 | Hood Cover | GI |
| 9 | Motor Cover | GI |
| 10 | Operator & Control | German Make Motor |
| 11 | Connecting Voltage | 400 V ~ / 50 - 60 Hz |
| 12 | Open-Stop-Close Button | Standarad |
| 13 | Protection Category | IP 54 |
| 14 | Power Consumption | 0.75 kw Motor |
| 15 | Emergency Off Button | Standard |
| 16 | Closing Zone Monitoring | Optical Safety edge |
| 17 | External Route Monitoring | Photocell |
| 18 | Emergency Opening | Crank Handle |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Single Skin Motorised Rolling Shutter**





| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Rolling Shutter | Rolling Shutter with Galvalume slat of thickness of 1.2 mm. |
| 2 | Mounting Location area | Inside area / Outside area |
| 3 | Curtain Panel | The panel made of 1.2 mm thick Galvalume slat |
| 4 | Curtain panel size | 75mm wide |
| 5 | Curtain Profile | Curved with perforation at 0.5 mtr |
| 6 | Bottom Profile | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 7 | Side Guide Profile | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) |
| 8 | Roller Shaft | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 9 | Side Brackets | MS Plate 3 mm to 10 mm thick, as per the opening dimension |
| 10 | Hood Cover | Made of GI Sheet Thickness 0.9 mm GI |
| 11 | Surface finish | Powder coated |
| 12 | Drive Unit & Mounting Type | Electic motor - In direct Mounting - IP 54 |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**NIHVA Make Dock Leveller**





| Sr. No. | Description | Specifications |
|---|---|---|
| 1 | Capacity | 15 Ton - UDL |
| 2 | Dock operation mode | AC power pack hydraulically operated |
| 3 | Lip operation mode | Hydraulic |
| 4 | Operation control | Through panel |
| 5 | Loading platform height from road | 1250mm |
| 6 | Travel above & below dock level | (+) 300 / (-) 150 mm |
| 7 | Platform Size (W x L) | 2000 mm x 2500 mm |
| 8 | Lip size (W x L ) | 2000 x 400 mm |
| 9 | Shut Height | 480 mm |
| 10 | Maximum slope can be achieved | 0.1 |
| 11 | Clear Pit dimensions (W x L x D) | (W) 2050mm x (L)2500 mm x (D)480 mm |
| 12 | Hydraulic power pack | Standard |
| 13 | Driver type | Direct by electric Motor |
| 14 | Motor Ratings | 1 H.P |
| 15 | Pump design flow | 2.5 LPM |
| 16 | Pump pressure | 120 bar Operating 200 bar Max. |
| 17 | Safety valve set pressure | 120 Kg/cm² |
| 18 | Pump Type | Gear |
| 19 | Volume of oil receiver | 7 Lit |
| 20 | No Of Deck cylinder | 2 No |
| 21 | Lip Cylinder | 1 No |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Boom Barrier**





| Sr. No. | Description | Specifications |
|---|---|---|
| 1 | Size | 5 Mtr / 8 Mtr |
| 2 | Model No | Michealangelo 60 |
| 3 | MICHELANGELO BT A Barrier | Opening Time- 6S |
| 4 | Slowdown | Adjustable |
| 5 | Motor Power Supply | 24V |
| 6 | Type of limit Switch | Electronic |
| 7 | Frequency of Use | Continous Use |
| 8 | Protection Rating | IP54 |
| 9 | Lock | Mechanical |
| 10 | Safety | Photo cell |
| | | Magnetic loop detector |
| | | Flashing Light |
| | | Mobile Support |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 10 -12 weeks for Rapid Rollup Door & 5-6 Weeks For Rolling Shutters , Boom Barrier and Dock Leveler from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr Shrikant Mirkute on 8551098333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd