NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Elringklinger Automotive Components (India) Pvt. Ltd
Plot No. G2, Ranjangaon Indl. Area,
Tal: Shirur, Dist.: Pune, Pin: 412 220

Date : 08.02.2021
Quote NO : SQT.20.21.3006
Kind Attn : Mr. Prashant Khandagale
Email Id : prashant.khandagale@elringklinger.com
Contact No: 9764007106

Subject : Quotation for NIHVA Make High Speed Door & ASSA ABLOY Make High Speed Door

Dear Sir /Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Option - 1

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY Make Rapid Roll Up Door -HS8010P**	4000	5000	1	783,000	783,000	20,000	20,000
				Total		**783,000**		**20,000**
2			P&F Charges	3%		**23,490**		
			Total Without Taxes			**806,490**		**20,000**
3			GST Extra @ 18%	18%		145,168		3,600
			Total With Taxes			**951,658**		**23,600**

Option - 2

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Rapid Roll Up Door**	4000	5000	1	410,000	410,000	20,000	20,000
				Total		**410,000**		**20,000**
2			P&F Charges	3%		**12,300**		
			Total Without Taxes			**422,300**		**20,000**
3			GST Extra @ 18%	18%		76,014		3,600
			Total With Taxes			**498,314**		**23,600**
			Transportation Charges			**Extra at Actual**		
			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification


ASSA ABLOY Make Rapid Roll Up Door



Sr. No	Description	Details
		High Speed Door HS8010P
1	Door construction:	The HS8010P is designed for exterior openings in medium-sized heavy-duty operations
2	Side Frames	Made up with Galvanised Steel Profiles. Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss
3	Door Curtain	• Door curtain 900 g/m² colored PVC, material thickness: 0,8 mm • Flexible door curtain without ridged parts. • The door curtain is available in 8 standard colors
4	Thermal transmittance:	(EN 12428) 6,02 W/(m²K)
5	Wind resistance:	(EN 12424) Class 4 (1000 Pa (N/m²))
6	Drive Unit :	1,5 KW. 400V, 3 Phase
7	Temperature range :	-20°C to +40°C
8	Operator protection:	IP65
9	Control system:	Control unit with display, impulse Up and Down buttons, an emergency stop mushroom button and a mechanical main switch
10	Speed:	Opening / closing up to 2,4 / 1,2 m/s. Depends on Door Size
11	Safety device:	• Flexible soft bottom edge including wireless edge activator. • Break-away and self-repair function.

NIHVA Make Rapid Roll Up Door





Specification	Description
Description	NIHVA Make Rapid Roll Up Door
Size	(W) 4000 mm x (H) 5000 mm
Wind Resistance	(EN 12424) Class 2
Basic Equipment :	High-Speed Roller Door with curtain and Standred RAL Colour. Door with curtain tension.
Drive Unit :	Motor IP 54, either RH or LH as an option, with control cable (standard length = height of door)
Control system :	ROBODOR MR380- frequency converter control system for opening/closing speed -0.8 to 3 M/s
Power supply :	3/(N)/PE/230/400/415 v; 50 Hz
Safety :	Safety contact edge, Safety photocell transmitter / receiver inside side columns.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9-10 Weeks for NIHVA Make HSD & 12-13 Weeks For ASSA ABLOY Make HSD from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd