NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Hettich India Pvt. Ltd.
302, Durolite House | Opp SAB TV, New Link Road
Mumbai-400053

Date : 28.08.2020
Quote NO : **SQT.20-21.2439**
Kind Attn : Mr.Nitin Juneja
Email Id : nitin.juneja@hettich.com
Contact No: 9205877118

Project Name & Location:Primary Packaging machine with Bowl feeder,Mumbai

Subject : Quotation for Primary Packaging machine with Bowl feeder

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Primary Packaging Machine	1	42,35,000.00	**42,35,000.00**	**85,650.00**	**85,650.00**
2	Bowl feeder 1 (D500)	1	1,29,630.00	**1,29,630.00**	**30,000.00**	**30,000**
	Bowl feeder 2 (D 400)	2	1,33,334.00	**2,66,668.00**		
	Linear Feeder	3	29,862.00	**89,586.00**		
	Flat belt conveyor	1	1,52,778.00	**1,52,778.00**		
		Total		**48,73,662.00**		**1,15,650**
3	P&F Charges	3%		**1,46,209.86**		
	Total Without Taxes			**50,19,871.86**		**1,15,650**
	GST Extra @ 18%	18%		**9,03,576.93**		**20,817.00**
	Total With Taxes			**59,23,448.79**		**1,36,467.00**
4	Transportation Charges			**In Client Scope**		
5	Unloading Charges @ Site			**In Client Scope**		

B) Technical Specification

1 **Primary Packaging machine**

Parameters	Specification
Product to pack	2 pieces of each -hinge, mounting plates and cover plate.
Output	30-40pcks/min.
Complete automation and control system	Beckhoff Germany.
VFD for conveyors	Lenze.
Pneumatics	SMC
Switch gears and electrical items	Schneider.
Cables	Lapp

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

2 **Bowl feeder**

Parameters	Specification
Product to pack	Bowl Feeder
Size	N500
Feed rate	50 nos / min

Product	Linear Feeder
Size	700 mm
Vibration frequency Adjustable	

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 8551093333.**

With Best Regards
Samruddhi
8530872333
For NIHVA Technologies Pvt Ltd